

## Pender County Planning and Community Development

#### **Planning Division**

805 S. Walker Street PO Box 1519 Burgaw, NC 28425



Phone: 910-259-1202 Fax: 910-259-1295 www.pendercountync.gov

## Oyster Creek Landing Application Information Major Site Development Plan

Case Number: SDP 2022-308

**Application Type:** Major Site Development Plan

Applicant: McKim & Creed

Owners: Hampstead Station, LLC

Location: At the southwest corner of the intersection of Hoover Road and US HWY 17.

**Property ID** #(s): 3282-98-7567-0000, 3282-98-8323-0000, 3282-98-5392-0000, 3282-98-

7116-0000, 3282-98-4294-0000 & 3282-98-6151-0000

**Description:** Commercial development including three buildings totaling 54,100 square feet.

**Current Zoning:** GB, General Business

#### **Technical Review Committee Meeting**

Thursday, November 3, 2022

#### **Board of County Commissioners/Planning Board Meeting**

N/A

#### **Application Materials**

Application Site Plan

## Pender County Planning and Community Development

#### **Planning Division**

805 S. Walker Street PO Box 1519 Burgaw, NC 28425



Phone: 910-259-1202 Fax: 910-259-1295 www.pendercountync.gov

#### MAJOR AND MINOR SITE DEVELOPMENT APPLICATION

		arca Plans	THIS SECTION	N FOR OFFICE	USE	18.00		
Date:	Permit Nu	mber:	Permit F	ee:	Invoice Nu	mber:	The state of	
*Zoning Approval O	NLY: YES / N	10	Final Zoi	ning Complia	nce Approved	: YES / I	NO / N/A	
Type of Site Develop	oment Plan:	I	Major	☐ Minor				
<b>SECTION 1: GEN</b>	<b>ERAL INFO</b>	RMATI	ON					
Applicant's Name:	McKim	& Cree	d	Proper Name:	ty Owner's	На	mpstead Statio	on, LLC
Applicant's Address:	243 No	orth Fror	nt Street	Proper Addres	ty Owner's s:	23	24 Pansy Stre	et
City, State, & Zip	Wilming	gton, NC	C 28401	City, S	tate, & Zip	Hu	untsville, AL 35	801
Phone Number:	910.34	3.1048		Phone	Number:	91	9.606.3100	
Email Address:			creed.com	Email	Address:	ldd	  12486@gmail	.com
Legal relationship land owner:	of applicant	t to	Consultant			*		
<b>SECTION 2: PRO</b>	JECT INFO	RMATI	ON					
PIN (Property Id #):	See belo	w - mult	tiple PINs	Total prop	erty acreage	):	5.11	
Zoning :	GB			Acreage to	be disturbe	ed:	6.0	
<b>Directions to Site:</b>	From W	ilmingto	n, North on	Hwy 17 for	about 6 m	les from	m 140 intercha	nge
	turn left	at light of	onto Hoove	r Road and	then turn le	eft into	rear entrance	to
,	McDona	ld's. Co	ntinue strai	ght onto dir	t road to ar	rive at	site.	
<b>Lot Size:</b> 222,592	SF (5.11 ac	) Sq	Ft of Buildin	<b>g:</b> 54,100 S	SF * Bui	lding H	eight: 39'-6"	
Setbacks Fron	t: 25'		Side: 1	0'		Rear: 1	0'	
NAICS Code/Use:	N/A							
<b>Business Name:</b>	Oyster Cr	eek Lan	nding					
<b>Describe activities</b>	to be	Propose	ed activities	are in align	nment with	current	zoning.	
undertaken on pro	_	Develop	oment is inte	ended as c	ommercial	space i	ncluding retail,	
Ownership:	None	general	office, and	restaurant	space.			
✓ Private  □ Public	Number of	BD	ees:	Number of I	Members: N/A		Seating Capacity:	TBD

PINs: 3282-98-7567-0000; 3282-98-8323-0000; 3282-98-5392-0000; 3282-98-7116-0000;

3282-98-4294-0000; 3282-98-6151-0000

<sup>\*</sup>If the applicant is not the owner of the property, a notarized letter from the property owner may be required

<sup>\*</sup>Zoning approval is for the use being proposed ONLY, other department approvals may be required i.e. Fire Marshal, Environmental Health, Permitting, etc...

SECTION 4: ADDIT	IONAL COMMENTS			1
* Three (3) building	as proposed on the site. Two of the bldgs are 2-story with 12	.150 sq.	ft. per	1
floor. The other bu	ilding is 5,500 sq. ft. $[(12,150 \text{ SF x 4}) + 5,500 \text{ SF} = 54,100 \text{ S}]$	F],	iii poi	1
Detailed site lighting	plan will be designed by DUKE and submitted prior to TRC a	pproval		
A portion of the site	is previously permitted for SWM via Permit # SW8 070226.			
SECTION 5: SIGNA				
Applicant:	1000	Date:	10-6-22	L
Owner:	Com 1 2 7:	Date:	10-6-2	1022
Planning Staff:		Date:		

#### Additional Comments continued:

Estimated Trip Generation: 2,184 Daily Trips 310 vph (AM Peak) 463 vph (PM Peak)

(Based from ITE Trip Gen. Manual 11th Edition Land Uses: 822 - Strip Retail Plaza <40K; 710 - General Office Building; and 932 - High Turnover (sit-down) Restaurant)


# SITE PLAN(S)

# OYSTER CREEK LANDING



# SDP 2022-305 PERMIT SET

US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA 06/07/2023



4 VICINITY MAP

SCALE: NOT TO SCALE

NAME:

## OYSTER CREEK LANDING

OWNER/DEVELOPER: HAMPSTEAD STATION, LLC 2324 PANSY STREET HUNTSVILLE, AL 35801 PHONE: (919) 606-3100 EMAIL: LDD12486@GMAIL.COM

243 N. FRONT STREET
WILMINGTON, NC 28401
PHONE: 910.343.1048
PROJECT MANAGER: RICHARD COLLIER, PE

PREPARED BY: MCKIM & CREED, INC

RCOLLIER@MCKIMCREED.COM
PROJECT ENGINEER: TRAE LIVICK, PE

TLIVICK@MCKIMCREED.COM


LANDSCAPE ARCHITECT: AMANDA MACLEOD, PLA'
AMACLEOD@MCKIMCREED.COM

SURVEYOR:
PORT CITY LAND SURVEYING, PLLC
1114 SHIPYARD BLVD.
WILMINGTON, NC 28412
STEVEN BUIE (910) 791-0080

PORTCITYLANDSURVEYING@GMAIL.COM

MATT ROBERTS, LS MROBERTS@MCKIMCREED.COM





C1.0 COVER C1.1 GENERAL NOTES C2.0 EXISTING CONDITIONS C2.1 DEMOLITION PLAN C2.2 TREE REMOVAL C3.0 SITE PLAN - OVERALL C4.0 EROSION CONTROL PLAN - STAGE 1 C5.0 EROSION CONTROL PLAN - STAGE 2 C7.0 GRADING AND DRAINAGE PLAN - OVERALL C7.1 STORM SCHEDULE C8.0 UTILITY PLAN - OVERALL C10.0 LANDSCAPE PLAN - OVERALL C11.1 SITE DETAILS C11.2 SITE DETAILS C12.0 EROSION CONTROL DETAILS C12.1 EROSION CONTROL DETAILS C12.2 EROSION CONTROL DETAILS C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL C13.5 SCM-2 DETAIL	NUMBER	TITLE						
C2.0 EXISTING CONDITIONS  C2.1 DEMOLITION PLAN  C2.2 TREE REMOVAL  C3.0 SITE PLAN - OVERALL  C4.0 EROSION CONTROL PLAN - STAGE 1  C5.0 EROSION CONTROL PLAN - STAGE 2  C7.0 GRADING AND DRAINAGE PLAN - OVERALL  C7.1 STORM SCHEDULE  C8.0 UTILITY PLAN - OVERALL  C10.0 LANDSCAPE PLAN - OVERALL  C11.0 SITE DETAILS  C11.1 SITE DETAILS  C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAIL	C1.0	COVER						
C2.1 DEMOLITION PLAN C2.2 TREE REMOVAL C3.0 SITE PLAN - OVERALL C4.0 EROSION CONTROL PLAN - STAGE 1 C5.0 EROSION CONTROL PLAN - STAGE 2 C7.0 GRADING AND DRAINAGE PLAN - OVERALL C7.1 STORM SCHEDULE C8.0 UTILITY PLAN - OVERALL C10.0 LANDSCAPE PLAN - OVERALL C11.0 SITE DETAILS C11.1 SITE DETAILS C11.2 SITE DETAILS C12.1 EROSION CONTROL DETAILS C12.1 EROSION CONTROL DETAILS C12.2 EROSION CONTROL DETAILS C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C1.1	GENERAL NOTES						
C2.2 TREE REMOVAL  C3.0 SITE PLAN - OVERALL  C4.0 EROSION CONTROL PLAN - STAGE 1  C5.0 EROSION CONTROL PLAN - STAGE 2  C7.0 GRADING AND DRAINAGE PLAN - OVERALL  C7.1 STORM SCHEDULE  C8.0 UTILITY PLAN - OVERALL  C10.0 LANDSCAPE PLAN - OVERALL  C11.0 SITE DETAILS  C11.1 SITE DETAILS  C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAIL	C2.0	EXISTING CONDITIONS						
C3.0 SITE PLAN - OVERALL  C4.0 EROSION CONTROL PLAN - STAGE 1  C5.0 EROSION CONTROL PLAN - STAGE 2  C7.0 GRADING AND DRAINAGE PLAN - OVERALL  C7.1 STORM SCHEDULE  C8.0 UTILITY PLAN - OVERALL  C10.0 LANDSCAPE PLAN - OVERALL  C11.0 SITE DETAILS  C11.1 SITE DETAILS  C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAILS	C2.1	DEMOLITION PLAN						
C4.0 EROSION CONTROL PLAN - STAGE 1 C5.0 EROSION CONTROL PLAN - STAGE 2 C7.0 GRADING AND DRAINAGE PLAN - OVERALL C7.1 STORM SCHEDULE C8.0 UTILITY PLAN - OVERALL C10.0 LANDSCAPE PLAN - OVERALL C11.0 SITE DETAILS C11.1 SITE DETAILS C11.2 SITE DETAILS C12.0 EROSION CONTROL DETAILS C12.1 EROSION CONTROL DETAILS C12.2 EROSION CONTROL DETAILS C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C2.2	TREE REMOVAL						
C5.0 EROSION CONTROL PLAN - STAGE 2 C7.0 GRADING AND DRAINAGE PLAN - OVERALL C7.1 STORM SCHEDULE C8.0 UTILITY PLAN - OVERALL C10.0 LANDSCAPE PLAN - OVERALL C11.0 SITE DETAILS C11.1 SITE DETAILS C11.2 SITE DETAILS C12.0 EROSION CONTROL DETAILS C12.1 EROSION CONTROL DETAILS C12.2 EROSION CONTROL DETAILS C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C3.0	SITE PLAN - OVERALL						
C7.0 GRADING AND DRAINAGE PLAN - OVERALL C7.1 STORM SCHEDULE C8.0 UTILITY PLAN - OVERALL C10.0 LANDSCAPE PLAN - OVERALL C11.0 SITE DETAILS C11.1 SITE DETAILS C11.2 SITE DETAILS C12.0 EROSION CONTROL DETAILS C12.1 EROSION CONTROL DETAILS C12.2 EROSION CONTROL DETAILS C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C4.0	EROSION CONTROL PLAN - STAGE 1						
C7.1 STORM SCHEDULE  C8.0 UTILITY PLAN - OVERALL  C10.0 LANDSCAPE PLAN - OVERALL  C11.0 SITE DETAILS  C11.1 SITE DETAILS  C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAIL	C5.0	EROSION CONTROL PLAN - STAGE 2						
C8.0 UTILITY PLAN - OVERALL  C10.0 LANDSCAPE PLAN - OVERALL  C11.0 SITE DETAILS  C11.1 SITE DETAILS  C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAIL	C7.0	GRADING AND DRAINAGE PLAN - OVERALL						
C10.0 LANDSCAPE PLAN - OVERALL  C11.0 SITE DETAILS  C11.1 SITE DETAILS  C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAIL	C7.1	STORM SCHEDULE						
C11.0 SITE DETAILS  C11.1 SITE DETAILS  C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAIL	C8.0	UTILITY PLAN - OVERALL						
C11.1 SITE DETAILS  C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAIL	C10.0	LANDSCAPE PLAN - OVERALL						
C11.2 SITE DETAILS  C12.0 EROSION CONTROL DETAILS  C12.1 EROSION CONTROL DETAILS  C12.2 EROSION CONTROL DETAILS  C13.0 GRADING AND DRAINAGE DETAILS  C13.1 GRADING AND DRAINAGE DETAILS  C13.2 GRADING AND DRAINAGE DETAILS  C13.3 GRADING AND DRAINAGE DETAILS  C13.4 SCM-1 DETAIL	C11.0	SITE DETAILS						
C12.0 EROSION CONTROL DETAILS C12.1 EROSION CONTROL DETAILS C12.2 EROSION CONTROL DETAILS C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C11.1	SITE DETAILS						
C12.1 EROSION CONTROL DETAILS C12.2 EROSION CONTROL DETAILS C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C11.2	SITE DETAILS						
C12.2 EROSION CONTROL DETAILS C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C12.0	EROSION CONTROL DETAILS						
C13.0 GRADING AND DRAINAGE DETAILS C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C12.1	EROSION CONTROL DETAILS						
C13.1 GRADING AND DRAINAGE DETAILS C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C12.2	EROSION CONTROL DETAILS						
C13.2 GRADING AND DRAINAGE DETAILS C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C13.0	GRADING AND DRAINAGE DETAILS						
C13.3 GRADING AND DRAINAGE DETAILS C13.4 SCM-1 DETAIL	C13.1	GRADING AND DRAINAGE DETAILS						
C13.4 SCM-1 DETAIL	C13.2	GRADING AND DRAINAGE DETAILS						
	C13.3	GRADING AND DRAINAGE DETAILS						
C13.5 SCM-2 DETAIL	C13.4	SCM-1 DETAIL						
i I	C13.5	SCM-2 DETAIL						
C14.0 UTILITY DETAILS	C14.0	UTILITY DETAILS						
C14.1 UTILITY DETAILS	C14.1	UTILITY DETAILS						
C17.0 LANDSCAPE DETAILS	C17.0	LANDSCAPE DETAILS						





#### PENDER COUNTY CERTIFICATIONS

APPROVED BY THE PENDER COUNTY UNIFIED DEVELOPMENT ORDINANCE ADMINISTRATOR

PENDER COUNTY UDO ADMINISTRATOR:

DER COUNT PODO APMINISTRATOR.

Date: 6.8.2023

SITE PLAN VALID FOR TWO (2) YEARS FROM APPROVAL DATE.

#### NOTES:

ESTIMATED GROSS TRIPS GENERATED: 1,008 DAILY TRIPS; 125 TRIPS AM PEAK; 139 TRIPS PM PEAK (ITE LU CODES: 710, 720, 822, & 932). TRAFFIC IMPACT ANALYSIS IS APPROVED BY WMPO / NCDOT AS OF MAY 31, 2023.

PROJECT INFORMATION

2 LOCATION MAP

SCALE: NTS

SHEET INDEX

56/02/20/30

- CONTRACTOR IS RESPONSIBLE FOR PLACING BARRICADES, USING FLAGMEN, ETC. AS NECESSARY TO INSURE SAFETY TO THE PUBLIC.
- THESE DRAWINGS SHOW INFORMATION OBTAINED FROM THE AVAILABLE RECORDS REGARDING PIPES. CONDUITS. TELEPHONE LINES. AND OTHER STRUCTURES AND CONDITIONS WHICH EXIST ALONG THE LINES OF WORK AND BELOW THE SURFACE OF THE GROUND. THE OWNER AND ENGINEER DISCLAIM ANY RESPONSIBILITIES FOR THE ACCURACY OR COMPLETENESS OF SAID INFORMATION, AND SUCH INFORMATION IS BEING SHOWN ONLY FOR THE CONVENIENCE OF THE CONTRACTOR WHO MUST VERIFY THE INFORMATION TO HIS OWN SATISFACTION DURING THE BIDDING AND CONSTRUCTION PHASES. IF THE CONTRACTOR RELIES ON SAID INFORMATION, HE DOES SO AT HIS OWN RISK. THE GIVING OF THE INFORMATION ON THE CONTRACT DRAWINGS WILL NOT RELIEVE THE CONTRACTOR OF HIS OBLIGATIONS TO SUPPORT AND PROTECT ALL PIPES, CONDUITS, TELEPHONE LINES, AND OTHER STRUCTURES, WHETHER ABOVE OR BELOW GRADE.
- SHOULD ANY DAMAGE OCCUR TO EXISTING UTILITIES, IT SHALL BE REPAIRED SOLELY AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR SHALL VERIFY EXISTING INVERTS PRIOR TO CONSTRUCTION OF UNDERGROUND UTILITIES. TEST PITTING OF EXISTING LINES PRIOR TO CONSTRUCTION, IF NECESSARY, SHALL BE COORDINATED WITH THE OWNER.
- ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL CONFORM TO THE DRAWINGS, PROJECT SPECIFICATIONS, AND LOCAL BUILDING CODES.
- ALL DISTURBED AREAS SHALL BE SMOOTHLY GRADED TO PROMOTE POSITIVE DRAINAGE AND STABILIZED WITH TOPSOIL. SEED. AND MULCH. IF SETTLEMENT OCCURS. TOPSOIL. SEEDING. AND MULCH SHALL BE REPEATED UNTIL SETTLEMENT SUBSIDES. (SEE EROSION AND SEDIMENT CONTROL DETAILS AND SPECIFICATIONS.)
- WATER MAINS WILL BE INSTALLED AT A DEPTH THAT WILL PROVIDE 36" COVER OVER THE PIPES BELOW PROPOSED GRADE UNLESS SHOWN OTHERWISE ON THESE PLANS OR DIRECTED OTHERWISE BY THE ENGINEER.
- 10. WHEREVER SEWER OR WATER MAINS CROSS ONE ANOTHER, A MINIMUM VERTICAL CLEARANCE OF 18" SHALL BE PROVIDED BETWEEN THE BOTTOM OF THE WATER PIPE AND THE TOP OF THE SEWER PIPE.
- 11. WHEREVER SEWER OR WATER MAINS RUN PARALLEL TO EACH OTHER, A MINIMUM HORIZONTAL SEPARATION OF 10' SHALL BE PROVIDED, OR 18" VERTICAL SEPARATION.
- 12. IF NEITHER OF THESE CONDITIONS (#10 OR #11 ABOVE) CAN BE MET, THEN THE SEWER SHALL BE CLASS 50 DIP, MINIMUM OF 20 LF CENTERED OVER THE CROSSING.
- 13. ALL WATER VALVES, BOXES, AND FIRE HYDRANT ASSEMBLES SHALL BE SET AND ADJUSTED TO FINISHED GRADE. SEE PENDER COUNTY UTILITY DETAIL SHEET C14.0
- 14. THE OWNER IS RESPONSIBLE FOR THE ACQUISITION OF ALL EASEMENTS, BOTH TEMPORARY AND PERMANENT.
- 15. THE CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL SURVEY CONTROL PRIOR TO STAKING OUT CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO PROCEEDING WITH WORK.
- 16. ANY PROPERTY LINE MONUMENTATION DISTURBED DURING CONSTRUCTION SHALL BE REPLACED SOLELY AT THE CONTRACTOR'S EXPENSE.
- 17. THE CONTRACTOR ASSUMES ALL RESPONSIBILITY FOR ANY DEVIATION FROM THESE PLANS.
- 18. ALL SELECT AND BORROW MATERIAL SHALL MEET CRITERIA SET FORTH BY SECTIONS 1016 AND 1018 OF THE NORTH CAROLINA DEPARTMENT OF TRANSPORTATION'S STANDARDS AND SPECIFICATIONS FOR ROADS AND STRUCTURES. SEE SECTION FOR PLACEMENT AND COMPACTION INFORMATION. CONTRACTOR SHALL COORDINATE MATERIAL SUITABILITY WITH PROJECT GEOTECH ENGINEER.
- 19. THE ENGINEER AND THE CONTRACTOR SHALL INSPECT ALL EXISTING PIPES USED IN THE FINAL DRAINAGE SYSTEM AND AGREE ON THE CONDITION OF THE PIPES PRIOR TO CONSTRUCTION. IF DAMAGE OCCURS TO THESE PIPES DURING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OR REPLACEMENT OF THE PIPE(S).
- 20. EXISTING PAVING, CONCRETE, AND OTHER UNSUITABLE MATERIALS INCLUDING UNDERCUT EXCAVATION SHALL NOT BE USED AS FILL MATERIAL (UNLESS APPROVED BY THE GEOTECHNICAL ENGINEER) AND SHALL BE DISPOSED OF OUTSIDE THE PROJECT LIMITS AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR IS RESPONSIBLE FOR ALL PERMITTING AND FEES FOR DISPOSAL.
- 21. ALL TREES, STUMPS, ROOT MAT, ETC. SHALL BE ENTIRELY REMOVED REGARDLESS OF DEPTH, BURIAL OF ORGANIC MATERIAL WITHIN THE PROJECT LIMITS IS NOT PERMITTED. OPEN BURNING OF DOWNED TREES AND STUMPS IS NOT PERMITTED. CHIPPED MATERIALS MUST BE REMOVED PRIOR TO THE PLACEMENT OF EMBANKMENT OR TOPSOIL. THE CONTRACTOR IS RESPONSIBLE FOR ALL PERMITTING AND FEES FOR DISPOSAL.
- 22. THE CONTRACTOR IS SOLELY RESPONSIBLE TO OBTAIN OFF-SITE SPOIL AREAS FOR DISPOSAL OF EXCESS AND/OR UNSUITABLE MATERIALS AS NECESSARY. OFF-SITE SPOIL AREAS MUST BE SUBMITTED TO THE ENGINEER AND APPLICABLE REGULATORY AGENCIES PRIOR TO UTILIZATION BY THE CONTRACTOR. NO AREAS DESIGNATED AS WETLANDS WILL BE PERMITTED FOR USE AS A DISPOSAL SITE. THE CONTRACTOR SHALL SUBMIT DOCUMENTATION TO THE ENGINEER THAT NO WETLANDS WILL BE IMPACTED. THE ENGINEER WILL NOT CONSIDER ANY DELAYS OR MONETARY CLAIMS OF ANY NATURE RESULTING FROM THE CONTRACTOR'S FAILURE OR DIFFICULTY IN FINDING NECESSARY DISPOSAL SITES TO MEET THE TIME FRAMES AND CAPACITIES REQUIRED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PLANS, PERMITS, EROSION AND SEDIMENT CONTROL MEASURES, ETC. REQUIRED BY THE APPROPRIATE REGULATORY AGENCIES FOR UTILIZING OFF-SITE SPOIL AREAS. THE CONTRACTOR SHALL CERTIFY TO THE ENGINEER THAT ALL REQUIRED PERMITS HAVE BEEN OBTAINED PRIOR TO UTILIZING THE OFF-SITE SPOIL AREAS. ALL COSTS FOR PROCURING AND UTILIZING THE OFF-SITE SPOIL AREAS ARE TO BE INCIDENTAL TO THE BASE BID.

#### MATERIALS AND EASEMENT NOTES:

- ALL CATCH BASINS ARE NCDOT STD 840.02/840.03
- ALL DROP INLETS ARE NCDOT STD 840.16/840.16
- ALL STORM DRAINAGE PIPING TO BE POLYPROPYLENE (HP STORM), UNLESS OTHERWISE NOTED
- ALL SANITARY SEWER LINES AND WATERLINES SHALL BE C-900 PVC, UNLESS OTHERWISE NOTED AND MEET PLURIS HAMPSTEAD, LLC SPECIFICATIONS
- WATER UTILITY IS PUBLIC PENDER COUNTY PUBLIC UTILITIES
- SANITARY SEWER MAIN IS PRIVATE PLURIS HAMPSTEAD, LLC

#### **DEMOLITION NOTES**

- THE CONTRACTOR SHALL VISIT THE SITE TO BECOME FAMILIARIZED WITH FIELD DEMOLITION CONDITIONS.
- .. THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER DISPOSAL OF ALL DEMOLISHED DEBRIS ASSOCIATED WITH THE PROJECT IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST GENERATED BY THE WORK, INCLUDING BUT NOT LIMITED TO DEMOLITION AND CONSTRUCTION ACTIVITIES. SITE VEHICULAR TRAFFIC AND RELATED OPERATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR HAVING ALL EXISTING UTILITIES LOCATED PRIOR TO BEGINNING ANY DEMOLITION. CONTRACTOR SHALL CONTACT NC ONE CALL AT LEAST 72 HOURS PRIOR TO BEGINNING CONSTRUCTION OR EXCAVATION TO HAVE EXISTING UTILITIES LOCATED.
- EXISTING UTILITIES AND STRUCTURES SHOWN, BOTH UNDERGROUND AND ABOVE GROUND, ARE BASED ON FIELD SURVEY AND THE BEST AVAILABLE RECORD DRAWINGS. THE CONTRACTOR SHALL VERIFY FIELD CONDITIONS PRIOR TO BEGINNING RELATED CONSTRUCTION. ANY DISCREPANCIES SHALL BE REPORTED TO THE OWNER'S REPRESENTATIVE AND ENGINEER IMMEDIATELY.
- THE CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF DISCONNECTING AND ABANDONING ALL EXISTING UTILITIES WITH THE OWNER UNLESS OTHERWISE NOTED. ALL EXISTING UTILITIES AND ASSOCIATED PIPING, ETC. NOT IN USE ON THE SITE SHALL BE PROPERLY ABANDONED AND REMOVED AS REQUIRED. COORDINATE WITH THE OWNER AND ENGINEER.
- THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ANY EXISTING UTILITIES THAT REMAIN IN SERVICE DURING DEMOLITION.
- : THE CONTRACTOR IS RESPONSIBLE FOR STABILIZATION OF ALL DISTURBED AREAS AND SLOPES ON AND OFF SITE IN ACCORDANCE WITH THE EROSION CONTROL MEASURES SPECIFIED ON THE PLANS AND IN THE SPECIFICATIONS. THE CONTRACTOR SHALL COORDINATE WITH THE OWNER TO DETERMINE WHO IS RESPONSIBLE FOR PROVIDING THE PERMANENT STABILIZATION MEASURES AND THE TYPE OF PERMANENT MEASURES PRIOR TO BEGINNING DEMOLITION AND CONSTRUCTION. THE PERMANENT STABILIZATION MEASURES SHALL BE IN PLACE AND ACCEPTABLE TO THE OWNER'S REPRESENTATIVE AND ENGINEER PRIOR TO PROJECT CLOSEOUT. COORDINATE INSPECTION WITH THE OWNER AND ENGINEER PRIOR TO PROJECT CLOSEOUT.
- . THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING AND CONTACTING THE OWNER'S REPRESENTATIVE FOR THE REQUIRED INSPECTIONS ON THE PROJECT.

#### EXCAVATION, GRADING, AND BACKFILLING NOTES

- ANY UNDERCUTTING IN GOOD SOIL SHALL BE REPLACED AND THE REPLACEMENT MATERIAL SHALL BE COMPACTED TO NINETY-FIVE (95) PERCENT OF MAXIMUM DENSITY OBTAINED AT OPTIMUM MOISTURE CONTENT, AS DETERMINED BY THE ASTM D 698 STANDARD PROCTOR TEST METHOD. IN THE EVENT THAT MATERIAL ENCOUNTERED AT PIPE GRADE, SUBGRADE OF PARKING OR ROADWAYS AND SUBGRADE OF BUILDING FOUNDATIONS IS FOUND TO BE SOFT, SPONGY, OR IN ANY OTHER WAY UNSUITABLE, THE CONTRACTOR SHALL NOTIFY THE GEOTECHNICAL ENGINEER IMMEDIATELY. SUCH UNSUITABLE MATERIAL SHALL BE REMOVED TO A DEPTH AS SPECIFIED BY THE GEOTECHNICAL ENGINEER AND REPLACED WITH A MINIMUM OF SIX (6) INCHES OF STONE OR AS DIRECTED BY THE GEOTECHNICAL ENGINEER.
- BEFORE BACKFILLING IS COMMENCED OVER PIPES AND OTHER INSTALLATIONS, EARTH FILL SHALL BE TAMPED SOLID AROUND AND ABOVE THE PIPE TO A DEPTH OF ONE (1) FOOT ABOVE THE TOP OF THE PIPE. CARE SHALL BE TAKEN TO PREVENT ANY DISTURBANCE TO THE PIPE OR DAMAGE TO NEWLY MADE JOINTS. THE FILLING OF THE TRENCH SHALL BE CARRIED OUT SIMULTANEOUSLY ON BOTH SIDES OF THE PIPES IN
- 3. THE MATERIAL FOR BACKFILLING SHALL BE FREE FROM ALL PERISHABLE AND OBJECTIONABLE MATERIALS. BEFORE PLACING ANY BACKFILL, ALL RUBBISH, FORM, BLOCKS, WIRES OR OTHER UNSUITABLE MATERIAL SHALL BE REMOVED FROM EXCAVATION. THE BACK-FILLING OVER PIPES SHALL BE PLACED IN LAYERS NOT OVER SIX (6) INCHES THICK AND COMPACTED TO A MINIMUM DENSITY OF NINETY-FIVE (95) PERCENT OF THE MAXIMUM DRY DENSITY AS DETERMINED BY THE MODIFIED PROCTOR COMPACTION TEST TO A DEPTH OF 12 INCHES BELOW FINISHED GRADE. THE LAST 12 INCHES OF BACKFILL SHALL BE PLACED IN LAYERS NOT OVER SIX (6) INCHES THICK AND COMPACTED TO A MINIMUM DENSITY OF NINETY-EIGHT (98) PERCENT OF THE MAXIMUM DRY DENSITY AS DETERMINED BY THE MODIFIED PROCTOR COMPACTION TEST.

#### STORM DRAINAGE AND GRADING NOTES

- IN ACCORDANCE WITH NC GENERAL STATUTES, NPDES REGULATIONS, AND NCDENR REQUIREMENTS, STORMWATER DISCHARGE OUTFALLS SHALL BE INSPECTED BY THE CONTRACTOR. INSPECTIONS SHALL BE PERFORMED BY THE CONTRACTOR AFTER EACH STORM EVENT OF 1/2 INCH OR GREATER, WITH ONE WEEKLY INSPECTION MINIMUM. NCDENR STANDARD INSPECTION REPORTS SHALL BE PREPARED AND SIGNED WITH COPIES PROVIDED TO THE OWNER, ARCHITECT, AND ENGINEER, BY THE CONTRACTOR.
- OUTLET PROTECTION SHALL BE INSTALLED AROUND OUTFALL. DEVICES SHALL BE CONSTRUCTED TO FINAL PROPOSED CONDITION UPON STABILIZATION OF CONTRIBUTING GROUND SURFACES AND REMOVAL OF SEDIMENT FROM STORM PIPES.
- . ALL DIMENSIONS AND GRADES SHOWN ON THE PLANS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY CONSTRUCTION MANAGER IF ANY DISCREPANCIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION FOR NECESSARY PLAN OR GRADE CHANGES. NO EXTRA COMPENSATION SHALL BE PAID TO CONTRACTOR FOR ANY WORK DONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY ON THESE PLANS IF SUCH NOTIFICATION HAS NOT BEEN GIVEN.
- . UNLESS OTHERWISE NOTED, GRADES AND SPOT ELEVATIONS NOTED ON PLANS INDICATE FINISHED GRADE OR PAVEMENT SURFACE. ALL DIMENSIONS ARE MEASURED TO THE FACE OF CURB UNLESS OTHERWISE INDICATED.
- STORM DRAINAGE PIPE AND STRUCTURE MATERIALS WITHIN NCDOT RIGHT OF WAY SHALL BE IN ACCORDANCE WITH NCDOT STANDARDS AND SPECIFICATIONS, LATEST
- 5. CONTRACTOR SHALL SUBMIT STORM DRAIN AND STRUCTURE MATERIALS SHOP DRAWING DOCUMENTS TO ENGINEER FOR REVIEW AND APPROVAL.

#### UTILITY NOTES

- SCHEDULE A PRE-CONSTRUCTION MEETING WITH PENDER COUNTY UTILITIES AND PLURIS HAMPSTEAD. LLC AT LEAST 48 HOURS PRIOR TO CONSTRUCTION OF WATER INFRASTRUCTURE AND SANITARY SEWER INFRASTRUCTURE, RESPECTIVELY.
- WATER INFRASTRUCTURE IS PRIVATE BEYOND THE PROPOSED 2" DOMESTIC AND 6" FIRE SERVICE ASSEMBLIES, SEE SHEET C8.0.
- BACKFLOW PREVENTION AND METERS SHALL BE PROVIDED FOR DOMESTIC WATER SERVICE (RPZ). DOMESTIC SERVICE BACKFLOW PREVENTER WILL BE LOCATED AS SHOWN ON THE UTILITY PLANS. INSTALLER OF BACKFLOW PREVENTERS MUST CONTACT PCU PRIOR TO INSTALLING UNITS TO GIVE PCU THE OPTION TO VERIFY INSTALLATION PROCEDURES.
- 3.1. REDUCED PRESSURE PRINCIPLE ASSEMBLY FOR DOMESTIC WATER SERVICE
- IF THE CONTRACTOR DESIRES PCU WATER FOR CONSTRUCTION HE SHALL APPLY IN ADVANCE FOR THIS SERVICE AND MUST PROVIDE A REDUCED PRESSURE ZONE (RPZ) BACKELOW PREVENTION DEVICE ON THE DEVELOPER'S SIDE OF THE WATER METER BOX.
- WATER: 1.5" & 2" PVC MAINS SHALL BE CONSTRUCTED USING ASTM D2241, IPS, GASKETED PIPE, SDR 21. 4"-12" PVC MAINS AND SERVICES SHALL BE CONSTRUCTED USING ASTM D1704, ASTM D2241 FOR SDR-21, CLASS 200 PVC.
- SANITARY SEWER: FOR PIPE SIZES 4" AND 6" PIPE SHALL BE SCH 40 CONFORMING TO THE REQUIREMENTS OF ASTM D1785 WITH SOLVENT WELD JOINTS CONFORMING TO ASTM D2672.
- FORCE MAIN: 2" FORCE MAIN RE-ALIGNMENT SHALL BE COORDINATED WITH PLURIS HAMPSTEAD, LLC. 2" DIAMETER FORCE MAIN MATERIAL SHALL BE PER PLURIS HAMPSTEAD, LLC MATERIALS STANDARDS AND SPECIFICATIONS
- WATER AND SEWER SERVICES CANNOT BE ACTIVATED ON NEW MAINS UNTIL ENGINEER'S CERTIFICATION AND AS-BUILTS ARE RECEIVED AND "FINAL APPROVAL" ISSUED BY PUBLIC WATER SUPPLY SECTION OF NCDENR AND "FINAL ENGINEERING CERTIFICATION" ISSUED BY DIVISION OF WATER QUALITY OF NCDENR.
- PVC WATER MAINS AND POLYETHYLENE SERVICES ARE TO BE MARKED WITH NO. 10 SINGLE STRAND INSULATED COPPER WIRE INSTALLED THE ENTIRE LENGTH AND STRAPPED TO THE PIPES WITH DUCT TAPE. THE INSULATED WIRE IS TO BE STRIPPED TO BARE WIRE AND SECURED TO ALL VALVES. THIS WIRE IS TO BE ACCESSIBLE AT ALL FIRE HYDRANTS AND WATER METER BOXES TO AID IN FUTURE LOCATION OF FACILITIES.
- UNDERGROUND UTILITIES: ALL NEW UTILITIES SHALL BE INSTALLED UNDERGROUND, EXCEPT WHERE SUCH PLACEMENT IS PROHIBITED OR DEEMED IMPRACTICAL BY THE UTILITY PROVIDER. UNDERGROUND TERMINAL FACILITIES & CONDUITS FOR SITE POWER SUPPLY AND SITE LIGHTING WITHIN THE SUBJECT SITE SHALL BE INSTALLED BY THE DEVELOPER. COORDINATE WITH POWER PROVIDER.
- MINIMUM OF 36" COVERAGE ABOVE ALL WATER MAINS AND WATER SERVICES.
- 12. MINIMUM OF 36" VERTICAL SEPARATION BETWEEN WATERLINES AND STORM DRAIN CURB INLETS
- 3. PLANS ARE IN COMPLIANCE WITH PENDER COUNTY PUBLIC UTILITIES TECHNICAL STANDARDS AND SPECIFICATIONS.

#### RELATION OF WATER MAINS TO SANITARY SEWERS:

- LATERAL SEPARATION OF SANITARY SEWERS AND WATER MAINS: WATER MAINS SHALL BE LAID AT LEAST 10 FEET LATERALLY FROM EXISTING OR PROPOSED SEWERS UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT A 10 FOOT LATERAL SEPARATION, IN WHICH CASE
- 1.1. THE WATER MAIN IS LAID IN A SEPARATE TRENCH, WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER, OR
- THE WATER MAIN IS LAID IN THE SAME TRENCH AS THE SEWER WITH THE WATER MAIN LOCATED AT ONE SIDE ON A BENCH OF UNDISTURBED EARTH, AND ABOVE THE TOP OF THE
- CROSSING A WATER MAIN OVER A SEWER MAIN: WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS OVER A SEWER THE WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 24 INCHES ABOVE THE TOP OF THE SEWER MAIN. UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT AN 18 INCH VERTICAL SEPARATION - IN WHICH CASE BOTH THE WATER MAIN AND THE SEWER MAIN SHALL BE CONSTRUCTED OF FERROUS MATERIALS AND WITH JOINTS THAT ARE EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING.
- CROSSING A WATER MAIN UNDER A SEWER MAIN: WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS UNDER THE SEWER MAIN SHALL BE CONSTRUCTED OF FERROUS MATERIALS WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING. THE WATER MAIN SHALL BE C-900 PVC ENCASED WITHIN A STEEL SLEEVE. REFERENCE PCU STANDARD SPECS AND DETAILS.
- CROSSING A SEWER MAIN/WATER MAIN OVER OR UNDER A STORM DRAIN: WHENEVER IT IS NECESSARY FOR A SEWER MAIN/WATER MAIN TO CROSS A STORM DRAIN PIPE. THE SEWER MAIN/WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE OUTSIDE OF THE SEWER MAIN/WATER MAIN NEAREST TO THE OUTSIDE OF THE STORM DRAIN PIPE SHALL MAINTAIN A 24 INCH CLEAR SEPARATION DISTANCE, OR THE SEWER MAIN SHALL EITHER BE CONSTRUCTED OF DUCTILE IRON PIPE OR ENCASED IN EITHER CONCRETE OR DUCTILE IRON PIPE FOR AT LEAST 5 FEET ON EITHER SIDE OF THE CROSSING. SEE NOTE 3 DIRECTLY ABOVE FOR WATER MAIN

#### DUKE POWER

MATERIALS.

- CONTRACTOR SHALL COORDINATE WITH DUKE POWER (JON MARSTON, SEE CONTACT INFO ON RIGHT SIDE OF THIS SHEET) TO SCHEDULE A PRE-CONSTRUCTION MEETING.
- CONTRACTOR RESPONSIBLE FOR INSTALLATION OF CONDUIT RUNS AND CONCRETE TRANSFORMER PADS.

#### PIEDMONT NATURAL GAS

- CONTRACTOR SHALL INVESTIGATE THE EXISTING DEPTH OF PNG GAS MAIN TO DETERMINE IF THERE IS AN ELEVATION CONFLICT WITH THE PROPOSED UTILITIES (STORM PIPE AND SEWER). REFER TO SHEET C2.0 AND 10' GAS LINE EASEMENT (DB 4742, PG 2928). CONTRACTOR SHALL COORDINATE FIELD CONDITIONS WITH ENGINEER AND PNG CONTACT, UTILITY CONTACT INFO PROVIDED IN UTILITY CONTACTS SECTION, THIS SHEET. ANY COSTS TO ADJUST PNG GAS MAIN WILL BE BILLED TO THE FINANCIALLY RESPONSIBLE PARTY FOR THE DEVELOPMENT.
- PNG WILL PERMIT INSTALLATION FO ASPHALT PAVEMENT AN DCONCRETE CURBING OVER THE PNG EASEMENT. ANY SHRUBS AND/OR BUSHES MAY BE PLANTED WITHIN THE EASEMENTS SO LONG AS THEY DO NOT HAVE A MATURE GROWTH EXCEEDING 6 FEET IN HEIGHT. ACCESS RIGHTS TO THE PNG EASEMENT WILL BE MAINTAINED IN ACCORDANCE WITH THE EASEMENT. ANY IMPROVEMENTS (ASPHALT, CURBING, LANDSCAPING, ETC.) CONSTRUCTED IN THE EASEMENT MAY BE DESTROYED BY PNG IN SERVICE TO PNG ASSETS AND REPLACEMENT COSTS OF IMPROVEMENTS WILL NOT BE INCURRED BY PNG.
- COVER FROM TOP OF PNG GAS MAIN TO FINISHED GRADE SHALL BE 30" OR GREATER.
- CONTRACTOR SHALL COORDINATE WITH LOCAL AT&T OSWF TECHNICIAN FOR ANY EXCAVATION ACTIVITIES THAT MAY IMPACT AT&T FACILITIES. OSWF TECHNICIAN SHOULD BE ON-SITE DURING ANY SUCH ACTIVITY. OSWF TECHNICIAN'S CONTACT INFO IS PROVIDED IN UTILITY CONTACTS SECTION, THIS SHEET.

#### **EROSION CONTROL NOTES**

- ANY GRADING BEYOND THE DENUDED LIMITS SHOWN ON THE PLAN IS A VIOLATION OF THE COUNTY EROSION CONTROL ORDINANCE AND IS SUBJECT TO
- GRADING MORE THAN ONE ACRE WITHOUT AN APPROVED EROSION CONTROL PLAN IS A VIOLATION OF STATE LAW AND IS SUBJECT TO A FINE. ANY BUILDER THAT ANTICIPATED THE DISTURBANCE OF MORE THAN ONE ACRE WILL BE REQUIRED TO GET AN EROSION CONTROL PERMIT FROM NCDENR - DLQ.
- GROUND COVER MUST BE PROVIDED ON EXPOSED SLOPES WITHIN 21 CALENDAR DAYS FOLLOWING COMPLETION OF ANY PHASE OF GRADING; AND, A PERMANENT GROUND COVER FOR ALL DISTURBED AREAS WITHIN 15 WORKING DAYS OR 90 CALENDAR DAYS (WHICHEVER IS SHORTER) FOLLOWING COMPLETION OF CONSTRUCTION OR DEVELOPMENT.
- ADDITIONAL MEASURES TO CONTROL EROSION AND SEDIMENT MAY BE REQUIRED BY A REPRESENTATIVE OF NCDENR - DLQ.
- 5. SLOPES SHALL BE GRADED NO STEEPER THAN 3:1.
- ADDITIONAL DEVICES MAY BE REQUIRED AS AGREED UPON BY THE FIELD INSPECTOR, ENGINEER, AND OWNER.
- 7. IF ACTIVE CONSTRUCTION CEASES IN ANY AREA FOR MORE THAN 15 WORKING DAYS OR 90 CALENDAR DAYS (WHICHEVER IS SHORTER), ALL DISTURBED AREAS MUST BE SEEDED, MULCHED, AND TACKED.
- WITHIN 24 HOURS FOLLOWING ANY RAIN EVENT. THE CONTRACTOR SHALL INSPECT AND REPAIR, AS NECESSARY, ALL DAMAGED EROSION CONTROL MEASURES.
- 9. ALL ACTIVITY AND INSTALLATION OF EROSION CONTROL MATTING WILL BE COMPLETE PRIOR TO ANY RAIN EVENT.

#### **EROSION CONTROL MAINTENANCE PLAN:**

- 1. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED AND REPAIRED, AS NECESSARY, EVERY SEVEN (7) DAYS AND WITHIN 24 HOURS OF EVERY ONE-HALF (0.5) INCH OR GREATER RAINFALL.
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- SEDIMENT SHALL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES ABOUT 0.5 FEET DEEP. THE SEDIMENT FENCE WILL BE REPAIRED OR REPLACED AS NECESSARY TO MAINTAIN A BARRIER.
- 4. ALL AREAS WILL BE FERTILIZED, RESEEDED AS NECESSARY, AND MULCHED ACCORDING TO SPECIFICATIONS IN THE VEGETATIVE PLAN TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER.
- STONE CONSTRUCTION ENTRANCE TO BE CLEANED WHEN SEDIMENT ACCUMULATIONS ARE VISIBLE OR SEDIMENT IS TRACKED ON TO THE PAVEMENT. STONE WILL BE PERIODICALLY TOP DRESSED WITH 2 INCHES OF #4 STONE TO MAINTAIN 6 INCH DEPTH. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS REQUIRED.
- INSPECT TEMPORARY DIVERSIONS AND CHECK DAMS ONCE A WEEK AND AFTER EVERY RAINFALL. IMMEDIATELY REMOVE SEDIMENT FROM THE FLOW AREA AND REPAIR THE DIVERSION RIDGE AND CHECK DAM. CAREFULLY CHECK OUTLETS AND MAKE TIMELY REPAIRS AS NEEDED. WHEN THE AREA PROTECTED IS PERMANENTLY STABILIZED, REMOVE THE RIDGE AND THE CHANNEL TO BLEND WITH THE NATURAL GROUND LEVEL AND APPROPRIATELY STABILIZE IT.
- INSPECT TEMPORARY SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2" OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN IT ACCUMULATES TO ONE-HALF THE DESIGN DEPTH. PLACE REMOVED SEDIMENT IN AN AREA WITH SEDIMENT CONTROLS.
- CHECK THE SEDIMENT BASIN EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE RISER AND POOL AREA.
- INSPECT INLETS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (0.5" OR GREATER) RAINFALL EVENT. CLEAR THE MESH WIRE OF ANY DEBRIS OR OTHER OBJECTS TO PROVIDE ADEQUATE FLOW FOR SUBSEQUENT RAINS. TAKE CARE NOT TO DAMAGE OR UNDERCUT THE WIRE MESH DURING SEDIMENT REMOVAL REPLACE STONE AS NEEDED. INLET PROTECTION SHOULD BE CLEANED OUT WHEN IT IS HALF FULL.
- 10. INSPECT BAFFLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY. BE SURE TO MAINTAIN ACCESS TO THE BAFFLES. SHOULD THE FABRIC OF A BAFFLE COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY. REMOVE SEDIMENT DEPOSITS WHEN IT REACHES HALF FULL TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE BAFFLES. TAKE CARE TO AVOID DAMAGING THE BAFFLES DURING CLEAN OUT. SEDIMENT DEPTH SHOULD NEVER EXCEED HALF THE DESIGNED STORAGE DEPTH. AFTER THE CONTRIBUTING DRAINAGE AREAS HAS BEEN PROPERLY STABILIZED, REMOVE ALL BAFFLE MATERIALS AND UNSTABLE SEDIMENT DEPOSITS, BRING THE AREA TO GRADE. AND STABILIZE IT.
- 11. INSPECT THE SKIMMER FOR CLOGGING. PULL THE SKIMMER TO THE SIDE OF THE BASIN AND REMOVE ANY DEBRIS. ALSO CHECK THE ORIFICE INSIDE THE SKIMMER AND THE ARM OR BARREL PIPE FOR CLOGGING; IF CLOGGED, REMOVE THE DEBRIS.

### NOTE (G.S. 113A-57 (2))

THE ANGLE FOR GRADED SLOPES AND FILLS SHALL BE NO GREATER THAN THE ANGLE THAT CAN BE RETAINED BY VEGETATIVE COVER OR OTHER ADEQUATE EROSION CONTROL DEVICES OR STRUCTURES. IN ANY EVENT, SLOPES LEFT EXPOSED WILL, WITHIN 21 CALENDAR DAYS OF COMPLETION OF ANY GRADING, BE PLANTED OR OTHERWISE PROVIDED WITH TEMPORARY OR PERMANENT GROUND COVER, DEVICES, OR STRUCTURES SUFFICIENT TO RESTRAIN EROSION.

#### FIRE PROTECTION NOTES

- HYDRANT MUST BE WITHIN 100' OF THE FDC.
- 2. THE FDC MUST BE WITHIN 40' OF FIRE APPARATUS PLACEMENT
- 3. LANDSCAPING OR PARKING CANNOT BLOCK OR IMPEDE THE FDC OR FIRE HYDRANTS. A 3-FOOT CLEAR SPACE SHALL BE MAINTAINED AROUND THE CIRCUMFERENCE OF THE HYDRANT AND FDC.
- 4. COMBUSTIBLE MATERIALS MAY NOT BE STORED OR ERECTED ONSITE WITHOUT PENDER COUNTY FIRE INSPECTOR APPROVAL
- 5. A MINIMUM OF 5' SHALL SEPARATE UNDERGROUND FIRE LINES OR PRIVATE WATER MAINS FROM UNDERGROUND UTILITIES
- 6. CONTRACTOR SHALL MAINTAIN AN ALL-WEATHER ACCESS TO ALL PORTIONS OF THE JOBSITE WHERE COMBUSTIBLES ARE PRESENT AT ALL TIMES DURING CONSTRUCTION.
- 7. FIRE DEPARTMENT ACCESS WIDTHS SHALL BE A MINIMUM OF 20-FEET UNLESS LESSER WIDTHS ARE APPROVED BY THE FIRE CODE OFFICIAL.
- 8. CONSTRUCTION DUMPSTER(S), DORMANT CONSTRUCTION EQUIPMENT, AND OTHER ENCUMBRANCES SHALL NOT BE LEFT IN THE ROADWAY AND CANNOT IMPEDE FIRE AND/OR EMERGENCY VEHICLES.
- 9. WATER SHALL BE TURNED ON TO FIRE HYDRANTS PRIOR TO ANY CONSTRUCTION OF THE PROPOSED BUILDINGS.

#### UTILITY COMPANY CONTACTS

DUKE/PROGRESS ENERGY (DISTRIBUTION): JON MARSTON (919) 429-2370

AT&T (BELLSOUTH): CHRISSY COSTON (910) 341-7664

LOCAL AT&T OSWF TECHNICIAN: GLENN BOCHENKO (910) 617-6601; GB0660@ATT.COM

AT&T SERVICES, INC. - MANAGER NETWORK SERVICES: CASEY JOHANSEN (860) 689-6559; CJ652@ATT.COM

TIME WARNER CABLE: ROBERT JOHN (910) 216-4494

PIEDMONT NATURAL GAS: CATHY PLEASANT (910) 512-9391

SANITARY SEWER: PLURIS HAMPSTEAD, LLC: NICK EVANS (910) 742-7404; KAARIN WILLIAMS (910) 218-7653

WATER SUPPLY: PENDER COUNTY PUBLIC UTILITIES: KATIE LEUBNER (910) 663-3776

#### COUNTY AND AGENCY CONTACTS

Pender County **Planning Department** 805 S Walker Street Burgaw, NC 28425 (910)341-3255 Contact: Justin Brantley 

(910) 796-7215

**Contact: Dan Sams** 

**Pender County Public Utilities** 

**Contact: Katie Leubner** 

**605 E Fremont St** 

(910) 259-0212

Burgaw, NC 28425

Email: dan.sams@ncdenr.gov

kleubner@pendercountync.gov

**NCDENR** 

**NCDOT Division 3 - District 1 Sediment and Erosion Control** 299 Wilmington Hwy 127 N Cardinal Dr. Jacksonville, NC 28540 Wilmington, NC 28405

## (910) 455-3777

**Division of Water Quality** 127 Cardinal Drive Ext. Wilmington, NC 28405 (910) 796-7336 **Contact: Tyler Benson** Email: Tyler.Benson@ncdenr.gov

Pluris Hampstead, LLC

**Sanitary Sewer** 

(910) 742-7404

**Contact: Nick Evans** 

Sneads Ferry, NC 28460

1095 NC-210

**FIRE MARSHAL - PENDER COUNTY Mark Haraway** (910) 259-1441 (910) 512-0967 mharaway@pendercountync.gov

#### **ELECTRONIC DISCLAIMER**

CAD FILES MAY BE REQUESTED BY CONTRACTOR. ELECTRONIC FILES ARE NON-CERTIFIED RECORDINGS OF PRINTED DOCUMENTS PREPARED BY MCKIM & CREED, INC. AND ARE NOT A PART OF THE CONTRACT DOCUMENTS. REQUESTOR WILL BE REQUIRED TO SIGN A DIGITAL WAIVER UPON REQUEST. ENGINEER WILL PROVIDE REQUESTED ELECTRONIC DOCUMENTS WITHIN ONE BUSINESS DAY TIME FRAME UPON RECEIPT OF SIGNED DIGITAL WAIVER.

REVISIONS



**SMCKIM&CREED** 243 North Front Street Wilmington, North Carolina 28401

Phone: (910)343-1048, Fax: (910)251-8282

www mckimcreed com

License: F-1222

HAMPSTEAD STATION, LLC


OYSTER CREEK LANDING

US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA


**GENERAL NOTES** 

SCALE DRAWN DCO/ALN DESIGNED ALM/THI HECKED ROJ. MGR.

VERTICAL:



I:\09110\0001\ENG\80-DRAWINGS\81\_PRODUCTION\_SHEETS\2\_WORKING\_DWGS\C2.0 EXISTING CONDITIONS.DWG ---- 06/07/2023 14:20:38



www.mckimcreed.com

I:\09110\0001\ENG\80-DRAWINGS\81\_PRODUCTION\_SHEETS\2\_WORKING\_DWGS\C5.0 EROSION CONTROL PLAN - STAGE 2.DWG ---- 06/07/2023 14:21:30

www.mckimcreed.com

I:\09110\00001\ENG\80-DRAWINGS\81\_PRODUCTION\_SHEETS\2\_WORKING\_DWGS\C7.0 GRADING AND DRAINAGE PLAN - OVERALL.DWG ---- 06/07/2023 14:21:50

Structu	ıre Table		Structu	ıre Table		
Structure Name	Details		Structure Name	Details		5
CI-1	RIM = 56.959 INV IN = 48.470 INV OUT = 48.371		DI-8	RIM = 57.542 INV OUT = 53.600	(ST)	
CI-1A	RIM = 57.463 INV IN = 48.900 INV OUT = 48.800		DI-9	RIM = 57.666 INV IN = 49.139 INV OUT = 49.040	(GT)	
	RIM = 58.323		DI-10	RIM = 57.498 INV OUT = 54.300	(((1))	
CI-2	INV IN = 49.650 INV IN = 54.092 INV IN = 49.650 INV OUT = 49.550		DI-11	RIM = 58.056 INV IN = 54.250 INV OUT = 54.200	(ST)	
CI-2A	RIM = 57.701 INV OUT = 53.519		DI-12	RIM = 58.109 INV IN = 54.650 INV OUT = 54.600	(GT)	
CI-3	RIM = 58.399 INV IN = 54.000 INV IN = 50.500 INV IN = 50.500 INV OUT = 50.268		DI-13	RIM = 58.617 INV IN = 54.330 INV IN = 55.000 INV OUT = 54.334	(GT)	
CI-3A	RIM = 58.119 INV OUT = 53.915		DI-14	RIM = 58.141 INV IN = 54.650 INV IN = 55.244	(ST)	
CI-4	RIM = 58.001 INV IN = 49.540 INV OUT = 49.440		DI-15	INV OUT = 54.613 RIM = 57.858 INV OUT = 54.920	(ST)	
CI-5	RIM = 56.761 INV IN = 50.214 INV OUT = 50.110	(ST)	RLCO-A	RIM = 59.416 INV IN = 55.330 INV OUT = 55.330	(ST)	
CI-6	RIM = 55.228 INV IN = 50.590 INV OUT = 50.590	(ST)	RLCO-B	RIM = 59.411 INV IN = 56.200 INV OUT = 56.109	(GT)	
CI-7	RIM = 58.990 INV OUT = 54.850	(ST)	RLCO-C	RIM = 59.122 INV IN = 57.140	(ST)	
DI-1	RIM = 57.907 INV IN = 47.845 INV IN = 52.512 INV OUT = 47.740	(ST)	RLCO-D	INV OUT = 57.138 RIM = 59.039 INV OUT = 57.500	(ST)	
DI-1A	RIM = 57.160 INV OUT = 52.910	(ST)	RLCO-E	RIM = 59.095 INV IN = 54.160 INV OUT = 54.157	(ST)	
DI-2	RIM = 58.624 INV IN = 51.548 INV OUT = 48.160	(ST)	RLCO-F	RIM = 59.371 INV IN = 55.500 INV OUT = 55.500		
DI-3	RIM = 58.174 INV OUT = 52.250	(ST)	RLCO-G	RIM = 59.236 INV IN = 56.700		
DI-4	RIM = 56.901 INV IN = 47.850 INV IN = 47.780	(GT)	RLCO-H	INV OUT = 56.700 RIM = 58.951		
	INV IN = 47.850 INV OUT = 47.676	(GT)		RIM = 58.641		
DI-4A	RIM = 56.222 INV OUT = 48.089	(61)	RLCO-I	INV IN = 54.500 INV OUT = 54.500		
DI-5	RIM = 58.272 INV IN = 51.100 INV OUT = 51.000	(GT)	RLCO-J	RIM = 57.927 INV IN = 55.500 INV OUT = 55.500		
DI-6	RIM = 58.183 INV IN = 51.600 INV IN = 51.600 INV OUT = 51.500	(GT)	RLCO-K	RIM = 58.271 INV IN = 55.800 INV OUT = 55.800		
DI-6A	RIM = 57.620 INV OUT = 52.200	(GT)	RLCO-L	RIM = 58.800 INV OUT = 56.200		
DI-7	RIM = 58.111 INV IN = 53.100 INV OUT = 53.000					
		I		NOTE:		

Structu	ure Table		Structu	ure Table		
Structure Name	Details		Structure Name	Details		
DI-8	RIM = 57.542 INV OUT = 53.600 RIM = 57.666	(ST)	RLCO-M	RIM = 59.383 INV IN = 55.100 INV IN = 55.100 INV OUT = 55.000		
DI-9 DI-10	INV IN = 49.139 INV OUT = 49.040 RIM = 57.498	(GT)	RLCO-N	RIM = 58.773 INV IN = 55.500 INV OUT = 55.500		
DI-11	INV OUT = 54.300 RIM = 58.056 INV IN = 54.250 INV OUT = 54.200	(ST)	RLCO-O	RIM = 59.390 INV IN = 55.850 INV OUT = 55.750		
DI-12	RIM = 58.109 INV IN = 54.650	(GT)	RLCO-P	RIM = 59.387 INV OUT = 56.500		
	INV OUT = 54.600 RIM = 58.617	(GT)	RLCO-Q	RIM = 58.334 INV OUT = 56.000		
DI-13	INV IN = 54.330 INV IN = 55.000 INV OUT = 54.334	(ST)	RLCO-R	RIM = 59.087 INV IN = 55.500 INV OUT = 55.500		
DI-14	RIM = 58.141 INV IN = 54.650 INV IN = 55.244 INV OUT = 54.613	(ST)	RLCO-S	RIM = 59.467 INV IN = 55.700 INV OUT = 55.695		
DI-15	RIM = 57.858 INV OUT = 54.920	(ST)	RLCO-T	RIM = 59.399 INV IN = 55.770 INV OUT = 55.772		
RLCO-A	RIM = 59.416 INV IN = 55.330 INV OUT = 55.330	(ST)	RLCO-U	RIM = 59.427 INV IN = 56.370 INV OUT = 56.366		
RLCO-B	RIM = 59.411 INV IN = 56.200 INV OUT = 56.109	(GT)	(GT)	(GT)	RLCO-V	RIM = 59.294 INV OUT = 56.692
RLCO-C	RIM = 59.122 INV IN = 57.140 INV OUT = 57.138	(ST)	RLCO-W	RIM = 59.389 INV IN = 56.170 INV OUT = 56.171		
RLCO-D	RIM = 59.039 INV OUT = 57.500	(ST)	RLCO-WA	RIM = 59.288 INV IN = 55.579 INV OUT = 55.530		
RLCO-E	RIM = 59.095 INV IN = 54.160 INV OUT = 54.157	(ST)	RLCO-X	RIM = 59.408 INV OUT = 56.854		
RLCO-F	RIM = 59.371 INV IN = 55.500		SCM-1-OUT	RIM = 58.572 INV OUT = 55.250		
1,00-1	INV OUT = 55.500		SCM-1A-IN	RIM = 58.405 INV IN = 54.000		
RLCO-G	RIM = 59.236 INV IN = 56.700 INV OUT = 56.700		SCM-1B-IN	RIM = 57.577		
RLCO-H	RIM = 58.951 INV OUT = 56.980		SCM 2 OUT	RIM = 57.589 RIM = 58.677		
RLCO-I	RIM = 58.641 INV IN = 54.500		SCM-2-OUT SCM-2A-IN	INV OUT = 55.000 RIM = 57.650 INV IN = 54.000		
RLCO-J	INV OUT = 54.500 RIM = 57.927 INV IN = 55.500 INV OUT = 55.500		SCM-2B-IN	RIM = 57.702 INV IN = 54.100 INV IN = 54.000		
	1 23. 00.000	l		l		

Structu	ıre Table
Structure Name	Details
Structure - (82)	RIM = 53.571
Structure - (83)	RIM = 53.488
Structure - (87)	RIM = 55.665
Structure - (88)	RIM = 54.666
Structure - (135)	RIM = 48.474 INV IN = 52.400
Structure - (137)	RIM = 52.452 INV IN = 55.100
SWMH-1	RIM = 58.383 INV IN = 47.462 INV OUT = 46.140
SWMH-2	RIM = 58.859 INV IN = 54.220 INV OUT = 54.215
SWMH-4	RIM = 57.128 INV IN = 47.550

		STOR	RM DRAINA	GE PIPI	E DATA TA	\BLE	
	FROM	ТО	LENGTH	SIZE	SLOPE	UPSTREAM INVERT	DOWNSTREAM INVERT
	SWMH-2	SCM-1A-IN	57.03'	24"	0.38%	54.22'	54.00'
	SWMH-1		4.61'	30"	0.43%	46.14'	46.12'
	SCM-2-OUT	Structure - (135)	29.82'	12"	8.72%	55.00'	52.40'
	SCM-1-OUT	Structure - (137)	25.68'	12"	0.58%	55.25'	55.10'
(HDPE)	RLCO-X	RLCO-W	78.56'	8"	0.87%	56.85'	56.17'
	RLCO-WA	DI-13	17.87'	12"	2.97%	55.53'	55.00'
(HDPE)	RLCO-W	RLCO-WA	111.52'	12"	0.53%	56.17'	55.58'
(HDPE)	RLCO-V	RLCO-U	37.15'	8"	0.87%	56.69'	56.37'
(HDPE)	RLCO-U	RLCO-T	99.30'	12"	0.60%	56.37'	55.77'
(HDPE)	RLCO-T	RLCO-S	11.94'	12"	0.60%	55.77'	55.70'
(HDPE)	RLCO-S	RLCO-R	32.50'	12"	0.60%	55.70'	55.50'
	RLCO-R	DI-14	31.12'	12"	0.82%	55.50'	55.24'
(HDPE)	RLCO-Q	RLCO-M	73.10'	12"	1.23%	56.00'	55.10'
(HDPE)	RLCO-P	RLCO-O	37.00'	8"	1.76%	56.50'	55.85'
(HDPE)	RLCO-O	RLCO-N	13.32'	8"	1.88%	55.75'	55.50'
(HDPE)	RLCO-N	RLCO-M	19.74'	12"	2.03%	55.50'	55.10'
	RLCO-M	DI-12	34.59'	12"	1.01%	55.00'	54.65'
(HDPE)	RLCO-L	RLCO-K	26.94'	8"	1.48%	56.20'	55.80'
(HDPE)	RLCO-K	RLCO-J	16.50'	8"	1.82%	55.80'	55.50'
(HDPE)	RLCO-J	RLCO-I	93.17'	12"	1.07%	55.50'	54.50'

		(	STORM DRA	AINAGE	PIPE DAT	A TABLE	
	FROM	то	LENGTH	SIZE	SLOPE	UPSTREAM INVERT	DOWNSTREAM INVERT
	RLCO-I	SCM-2B-IN	39.68'	12"	1.01%	54.50'	54.10'
(HDPE)	RLCO-H	RLCO-G	11.53'	8"	2.43%	56.98'	56.70'
(HDPE)	RLCO-G	RLCO-F	60.80'	12"	1.97%	56.70'	55.50'
(HDPE)	RLCO-F	RLCO-E	125.97'	12"	1.06%	55.50'	54.16'
(HDPE)	RLCO-E	CI-3	13.99'	12"	1.12%	54.16'	54.00'
(HDPE)	RLCO-D	RLCO-C	5.64'	8"	6.38%	57.50'	57.14'
(HDPE)	RLCO-C	RLCO-B	46.88'	8"	2.00%	57.14'	56.20'
(HDPE)	RLCO-B	RLCO-A	77.94'	12"	1.00%	56.11'	55.33'
(HDPE)	RLCO-A	CI-2	123.73'	12"	1.00%	55.33'	54.09'
	DI-15	DI-14	75.97'	15"	0.36%	54.92'	54.65'
	DI-14	DI-13	80.84'	18"	0.35%	54.61'	54.33'
	DI-13	SWMH-2	32.46'	18"	0.35%	54.33'	54.22'
	DI-12	DI-11	67.94'	15"	0.52%	54.60'	54.25'
	DI-11	SCM-2A-IN	21.81'	15"	0.92%	54.20'	54.00'
	DI-10	SCM-2B-IN	45.75'	12"	0.66%	54.30'	54.00'
	DI-9	DI-4	47.76'	24"	2.49%	49.04'	47.85'
	DI-8	DI-7	50.71'	15"	0.99%	53.60'	53.10'
	DI-7	DI-6	131.20'	15"	1.07%	53.00'	51.60'
	DI-6A	DI-6	51.22'	15"	1.17%	52.20'	51.60'
	DI-6	DI-5	39.92'	18"	1.00%	51.50'	51.10'
ı							

	STORM DRAINAGE PIPE DATA TABLE										
		STORIND	KAINAC	E PIPE D/	ATA TABLE						
FROM	ТО	LENGTH	SIZE	SLOPE	UPSTREAM INVERT	DOWNSTREAM INVERT					
DI-5	CI-3	37.11'	18"	1.35%	51.00'	50.50'					
DI-4A	DI-4	61.89'	15"	0.50%	48.09'	47.78'					
DI-4	SWMH-4	25.19'	24"	0.50%	47.68'	47.55'					
DI-3	DI-2	89.99'	15"	0.78%	52.25'	51.55'					
DI-2	DI-1	73.55'	18"	0.43%	48.16'	47.84'					
DI-1A	DI-1	56.99'	15"	0.70%	52.91'	52.51'					
DI-1	SWMH-1	50.83'	24"	0.55%	47.74'	47.46'					
CI-7		11.66'	15"	0.60%	54.85'	54.78'					
CI-6	CI-5	67.42'	15"	0.56%	50.59'	50.21'					
CI-5	CI-4	115.95'	15"	0.49%	50.11'	49.54'					
CI-4	DI-9	58.32'	18"	0.52%	49.44'	49.14'					
CI-3A	CI-3	41.08'	15"	8.31%	53.92'	50.50'					
CI-3	CI-2	84.91'	18"	0.73%	50.27'	49.65'					
CI-2A	CI-2	45.04'	15"	8.59%	53.52'	49.65'					
CI-2	CI-1A	54.96'	18"	1.18%	49.55'	48.90'					
CI-1A	CI-1	33.03'	18"	1.00%	48.80'	48.47'					
CI-1	DI-4	52.09'	24"	1.00%	48.37'	47.85'					
	CI-6	10.94'	18"	0.91%	50.69'	50.59'					

STORM DRAIN SCHEDULE ROWS WITH (HDPE) TEXT POSITIONED TO THE LEFT OF THE ROW INDICATES THAT THE PIPE MATERIAL SHALL BE: HDPE - DOUBLE WALLED; SMOOTH INSIDE WALL.

STORM DRAIN STRUCTURE SCHEDULE ROWS WITH (ST) POSITIONED TO THE LEFT ARE SOLID TOP INLINE DRAINS, SEE DETAIL 1/C13.3.

STORM DRAIN STRUCTURE SCHEDULE ROWS WITH (GT) POSITIONED TO THE LEFT ARE GRATE TOP INLINE DRAINS, SEE DETAIL 1/C13.3.

STORM SCHEDULE



**SMCKIM&CREED** 

243 North Front Street Wilmington, North Carolina 28401 Phone: (910)343-1048, Fax: (910)251-8282

www.mckimcreed.com

HAMPSTEAD STATION, LLC


OYSTER CREEK LANDING US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA

STORM SCHEDULE

VERTICAL:


www.mckimcreed.com


REVISIONS




1:\09110\0001\ENG\80-Drawings\81 Production Sheets\2 Working Dwgs\C10.0 LANDSCAPE PLAN - OVERALL.dwg. 6/7/2023

1:\09110\00001\ENG\80-DRAWINGS\81\_PRODUCTION\_SHEETS\2\_WORKING\_DWGS\C10.0 LANDSCAPE PLAN - OVERALL.DWG ---- 06/07/2023 14:22:24







I:\09110\0001\ENG\80-DRAWINGS\81\_PRODUCTION\_SHEETS\2\_WORKING\_DWGS\C11.0 SITE DETAILS.DWG ---- 06/07/2023 14:23:33

#### **SEEDBED PREPARATION:**

- I.  $\,$  CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF AVAILABLE. RIP THE ENTRANCE AREA TO 6 INCHES DEPTH.
- 3. REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE REASONABLY SMOOTH AND UNIFORM.
- 4. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL (SEE BELOW\*).
- 5. CONTINUE TILLAGE UNTIL A WELL PULVERIZED, FIRM, REASONABLY UNIFORM SEEDBED IS PREPARED 4 TO 6
- 6. SEED ON A FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
- . MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH. 8. INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 60% DAMAGED, REESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER AND
- 9. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.
- AGRICULTURAL LIMESTONE 2 TONS/ACRE FERTILIZER - 1000 LBS/ACRE (10-10-10) SUPERPHOSPHATE - 500 LBS/ACRE (20%) MULCH - 2 TONS/ACRE (SMALL GRAIN STRAW) ANCHOR - ASPHALT EMULSION AT 450 GAL/ACRE

PERMANENT	<u>SEEDING</u>			
GRASS TYPE	AMOUNT/ 1000 S.F.	TIME OF SEEDING	INITIAL	
BERMUDA, COMMON	1-2 LBS.	APRIL – JUNE	25 LBS. 10-10-	
FESCUE, TALL (KENTUCKY 31)	5-7 LBS	JUNE — AUGUST FEB. — OCT.	25 LBS 10-10-	
SERICEA				

1-2 LBS | MARCH - APRIL | 25 LBS 10-10-10


LESPEDEZA

(SLOPES

TEMPORARY SEEDING  GRASS TYPE  AMOUNT/ 1000 S.F.			
GRASS TYPE		TIME OF SEEDING	INITIAL
RYE GRAIN	1-2 LBS.	APRIL – JUNE	25 LBS. 10-10-10
BROWNTOP MILLET	1-2 LBS	JUNE - AUGUST	25 LBS 10-10-10


#### TREE PROTECTION NOTES:

- NO LAND DISTURBANCE INCLUDING TREE REMOVAL IS TO OCCUR OUTSIDE THE LIMITS OF DISTURBANCE SHOWN ON THE PLANS. PROTECTIVE FENCING IS TO BE PROPERLY MAINTAINED THROUGHOUT THE DURATION OF THE PROJECT.
- 2. ANY TREES AND/OR AREAS DESIGNATED TO BE PROTECTED MUST PROPERLY BARRICADED WITH FENCING AND PROTECTED THROUGHOUT CONSTRUCTION TO INSURE THAT NO CLEARING AND GRADING OR STAGING OF MATERIALS WILL OCCUR IN THOSE AREAS.



NOTES:


### **GENERAL NOTES**




		•				•			
							TEMPORARY RO	CK CHECK DA	MS/WATTLES
TDD	SECONDARY	MANNING	VELOCITY		WATER	DITCH MIN.	CHECK DAM	NUMBER	NUMBER
NUMBER	LINING	n	(FPS)	COMMENT	DEPTH (IN)	DEPTH (IN)	SPACING (FT)	REQUIRED	PROVIDED
TDD 1	EXCELSIOR	0.035	1.25	EXCELSIOR OK	5.1	18	669	1	1

1. TEMP. DIVERSION DITCHES SHALL DRAIN INTO SEDIMENT BASINS, AND SEDIMENT TRAPS AND NOT OFF-SITE AS SHOWN 2. LINING SHALL BE EXCELSIOR MATTING AND INSTALLED ACCORDING TO NCDENR STD. EROSION CONTROL PRACTICES. 3. INSPECT TEMPORARY DIVERSIONS ONCE A WEEK AND AFTER EVERY RAINFALL. IMMEDIATELY REMOVE SEDIMENT FROM THE FLOW AREA AND REPAIR THE DIVERSION RIDGE. CAREFULLY CHECK OUTLETS AND MAKE TIMELY REPAIRS AS NEEDED. WHEN THE AREA PROTECTED IS PERMANENTLY STABILIZED, REMOVE THE RIDGE AND THE CHANNEL TO

## 2' MIN COMPACTED 18" MIN. - 2:1 SLOPE (MAX) **CROSS SECTION**




## 5 DANDY SACK INTLET PROTECTION NTS



NTS

### TEMPORARY DIVERSION DITCHES


BLEND WITH THE NATURAL GROUND LEVEL AND APPROPRIATELY STABILIZE IT.




#### NOTES:

- PLACE STONE TO THE LINES AND DIMENSIONS SHOWN IN THE PLAN ON A FILTER FABRIC FOUNDATION.
- KEEP THE CENTER STONE SECTION AT LEAST 9 INCHES BELOW NATURAL GROUND LEVEL WHERE THE DAM ABUTS THE CHANNEL BANKS.
- EXTEND STONE AT LEAST 1.5 FEET BEYOND THE DITCH BANK TO KEEP WATER FROM CUTTING AROUND THE ENDS OF THE CHECK DAM. SET SPACING BETWEEN DAMS TO ASSURE THAT THE ELEVATION AT THE TOP OF THE LOWER DAM IS THE SAME AS THE TOE ELEVATION OF THE UPPER DAM.
- PROTECT THE CHANNEL AFTER THE LOWEST CHECK DAM FROM HEAVY FLOW THAT COULD CAUSE EROSION. MAKE SURE THAT THE CHANNEL REACH ABOVE THE MOST UPSTREAM DAM IS STABLE
- ENSURE THAT OTHER AREAS OF THE CHANNEL, SUCH AS CULVERT ENTRANCES BELOW THE CHECK DAMS, ARE NOT SUBJECT TO DAMAGE OR
- BLOCKAGE FROM DISPLACED STONES.

**CHECK DAM** 



# SILT FENCE OUTLET



### NOTES:

1. DRIVE 5-FOOT STEEL POSTS (1.25 lb/lf steel) 2 FEET INTO THE GROUND SURROUNDING THE INLET. SPACE POSTS EVENLY AROUND THE PERIMETER OF THE INLET, A MAXIMUM OF 4 FEET APART.


SURROUND THE POSTS WITH AT LEAST 19-GAUGE HARDWARE CLOTH

WITH A 1/4-INCH MESH OPENING. SECURE THE WIRE MESH TO THE STEEL POSTS AT THE TOP, MIDDLE, AND BOTTOM FOR A MIN. 2 FEET ABOVE THE GROUND. PLACING A 2-FOOT FLAP OF THE WIRE MESH UNDER THE GRAVEL FOR ANCHORING AND REMOVAL IS RECOMMENDED. UNIFORMLY GRADE A SHALLOW DEPRESSION APPROACHING THE INLET THE TOP ELEVATION OF THE STRUCTURE MUST BE AT LEAST 12-INCHES LOWER THAN THE SURROUNDING GROUND ELEVATION DOWNSLOPE FROM THE INLET TO ENSURE THAT STORM FLOWS GET INTO THE INTENDED INLET; UNLESS OTHER SEDIMENT-CONTROL DEVICES ARE

INSTALLED TO PREVENT OFF-SITE SEDIMENT-RUNOFF.

#### HARDWARE CLOTH AND GRAVEL INLET PROTECTION

# 8' MAX. STD. STRENGTH FABRIC W/ WIRE FENCE 6' MAX. STD. STRENGTH FABRIC W/O WIRE FENCE **ELEVATION** STEEL POST



S	SILT FENCE	CALCULA	TION TABL	Æ			
SILT FENCE	Drainage	Length	Acre	0.25 Acre			
No.	Area		per 100 ft	per 100 ft			
	ac	ft		YES/NO			
PHASE 1 SILT FENCE							
SF 1	0.40	210	0.19	YES			
SF 2	0.14	320	0.04	YES			

#### NOTES:


1. WIRE FENCE (IF USED) SHALL BE MINUMUM 14 GAUGE WITH A MAXIMUM MESH OPENING OF 6-INCHES.

2. SYNTHETIC FILTER FABRIC OF AT LEAST 95% BY WEIGHT OF POLYOLEFINS OR POLYESTER, WHICH IS CERTIFIED BY THE MANUFACTURER OR SUPPLIER AS CONFORMING TO THE REQUIREMENTS IN ASTM D 6461 AND ALSO SHOULD CONTAIN ULTRAVIOLET RAY INHIBITORS AND STABILIZERS ACCORDING TO ASTM D 4355.

3. SEE THE NC EROSION CONTROL MANUAL FOR SPECIFICATIONS INSTALLING SEDIMENT FENCE USING THE SLICING METHOD MACHINERY

### 2 | TEMPORARY SILT FENCING

NTS



CONSTRUCTION ENTRANCE

# OYSTER CREEK LANDING US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA

DCO/ALN

NTS




6 GUTTERBUDDY


**SMCKIM&CREED** Wilmington, North Carolina 28401 Phone: (910)343-1048, Fax: (910)251-8282


www.mckimcreed.com

HAMPSTEAD STATION, LLC

**EROSION CONTROL DETAILS** 







#### NOTES:

- 1. BAFFLE MATERIAL SHALL BE MATERIALS SUCH AS 700 G/M COIR EROSION BLANKET, COIR MESH, OR TREE PROTECTION FENCE FOLDED OVER TO REDUCE PORE SIZE.
- 2. THE BAFFLE MATERIAL NEEDS TO BE SECURED AT THE BOTTOM AND SIDES USING STAPLES OR BY TRENCHING AS FOR SILT FENCE.
- 3. LOCATE THE EMERGENCY SPILLWAY ON NATURAL SOILS. AVOID PLACING IT THROUGH FILL
- MATERIAL WHEREVER POSSIBLE. 4. ALL RUNOFF MUST DISCHARGE TO THE INLET SIDE OF THE BASIN. DISCHARGE RUNOFF INTO THE BASIN IN A MANNER THAT MINIMIZES EROSION.

#### NOTES:


- 1. Q10 PEAK FLOW WERE TAKEN FROM RATIONAL METHOD.
- 2. REQUIRED SURFACE AREAS AND VOLUMES WERE TAKEN FROM NCDENR ESC MANUAL.
- 3. FAIRCLOTH SKIMMER SELECTION TABLE TAKEN FROM TABLE 4-2. NCDOT LEVEL III-A DESIGN OF SEDIMENT & EROSION CONTROL PLANS MANUAL
- 4. EMERGENCY WEIR WIDTH TAKEN FROM SKIMMER BASIN CRITERIA SECTION OF NCDENR ESC MANUAL TABLE AND/OR HYDRAULIC ROUTING OF THE BASIN TO ENSURE NON-EROSIVE VELOCITY.
- 5. MINIMUM BARREL PIPE ON THE SKIMMER IS 4-INCHES. (ON A 1% SLOPE THE CAPACITY IS 100

TEMPORARY SKIMMER SEDIMENT BASIN

PLASTIC OR

VARIABLE AS DIRECTED BY THE ENGINEER


WARNING SIGN



		BAFFLE 3=75% X E	BASIN WIDTH								
SKIMMER BASIN CALCULATION TABLE											
Skimmer No.	Drainage Area	Rational C Runoff Coeff.	I10 Intensity	Q10 Peak Flow	Required SA (435 x Q10)	Provided SA	Required Vol (1800cf/ac x DA)	Provided Vol	Storage Depth	Storage Vol Drained	Weir Width
	ac		in/hr	cfs	sf	sf	cf	cf	ft	cf	ft
TSB-1	1.58	0.40	7.63	4.83	2,102	2,557	2,851	8,673	2.00	2,851	8.0
TSB-2	2.27	0.40	7.63	6.92	3,009	3,071	4,080	7,689	2.00	4,080	8.0
TSB-3	1.88	0.63	7.63	9.03	3,926	6,685	3,380	16,646	2.00	3,380	10.0

	FAIRCLOTH SKIMMER SIZE CALCULATION								LET PARAM	METERS
Skimmer	Dewatering	Skimmer	Skimmer	Orifice	Orifice	Barrel	Barrel	Skimmer Basin	Orifice	Temp. Emergency
No.	Time	Outflow	Size	Diameter	Radius	Outflow	Pipe	<b>Bottom Elevation</b>	Elevation	Spillway Elev
	(days)	cf/day	in	in	in	gpm	in	ft	ft	ft
TSB-1	3	950	1.5	1.1	0.5	4.9	4.0	52.0	53.0	55.0
TSB-2	3	1,360	1.5	1.3	0.6	7.1	4.0	54.0	54.0	56.0
TSB-3	3	1,127	1.5	1.2	0.6	5.9	4.0	44.0	54.0	56.0

 $\overline{\hspace{0.5cm}}$  . TSB-3 SKIMMER BASIN IS IN SAME FOOTPRINT AS PERMAMENT SCM WET POND. CONNECT TEMPORARY FAIRCLOTH SKIMMER TO PERMANENT WET POND OUTLET STRUCTURE.





RIPRAP LOCATIONS	RIP-RAP API	RON SCHEDULE	
	Outlet pipe diameter 15 in.	Apron Length = $5.0 \text{ ft.}$	
SCM-1 (AKA - TSB-3)	Outlet flowrate 7.0 cfs	Apron Width = 3.8 ft.	
	Outlet velocity 5.7 ft/sec	Max Stone Dia = 6 in.	
	Material = Class A	Thickness = 9 in.	


- IN A WELL-DEFINED CHANNEL EXTEND THE APRON UP THE CHANNEL BANKS TO AN ELEVATION OF 6" ABOVE THE MAXIMUM TAILWATER DEPTH OR TO THE TOP OF THE BANK, WHICHEVER IS LESS.
- REINFORCEMENT SHALL CONFORM TO THE REQUIREMENTS OF REINFORCED CONCRETE PIPE OF LIKE DIAMENTER PER AASHTO M170, TABLE 2, WALL B. ALL CONCRETE TO BE 4000 P.S.I COMPRESSIVE STRENGTH.
- PROVIDE TONGUE OR SPIGOT JOINT AT INLET END SECTION. PROVIDE GROOVE OR BELL JOINT AT OUTLET END SECTION.

BAFFLE COIR DETAILS

THE DIMENSIONS FOR END SECTIONS SHALL SUBSTANTIALLY AGREE WITH THE TABLE BELOE. MINOR VARIATIONS WILL BE PERMITTED BASED ON THE MANUFACTURER'S STANDARD FORMS AND TEMPLATES. NOT TO BE USED IN NCDOT MAINTAINED RIGHT OF WAY.







2A PIPE OUTLET PROTECTION

TREE PROTECTION FENCING

OYSTER CREEK LANDING

FAIRCLOTH SKIMMER

**EROSION CONTROL DETAILS** 

US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA

SCALE **HORIZONTAL** DRAWN DCO/ALN VERTICAL:

SDP 2022-305 PERMIT SET

**REVISIONS** 



**SMCKIM&CREED** Wilmington, North Carolina 28401

www.mckimcreed.com

Phone: (910)343-1048, Fax: (910)251-8282

HAMPSTEAD STATION, LLC

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

FIGURE LISTEN REPORTS IN 1920 IN 1920

OILETS
portable toilets on level ground, at least 50 feet away from storm drains, as or wetlands unless there is no alternative reasonably available. If 50 foot is not attainable, provide relocation of portable toilet behind silt fence or place ravel pad and surround with sand bags.

e staking or anchoring of portable toilets during periods of high winds or in high affic areas.
or portable toilets for leaking and properly dispose of any leaked material.
a licensed sanitary waste hauler to remove leaking portable toilets and replace roperly operating unit.

Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
 Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
 Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground wa or surface water. If a spill occurs, clean area immediately.
 Do not stockpile these materials onsite.

ABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts.  If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	<ol> <li>Identification of the measures inspected,</li> <li>Date and time of the inspection,</li> <li>Name of the person performing the inspection,</li> <li>Indication of whether the measures were operating properly,</li> <li>Description of maintenance needs for the measure,</li> <li>Description, evidence, and date of corrective actions taken.</li> </ol>
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	<ol> <li>Identification of the discharge outfalls inspected,</li> <li>Date and time of the inspection,</li> <li>Name of the person performing the inspection,</li> <li>Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration,</li> <li>Indication of visible sediment leaving the site,</li> <li>Description, evidence, and date of corrective actions taken.</li> </ol>
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made:  1. Actions taken to clean up or stabilize the sediment that has left the site limits,  2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made:  1. Description, evidence and date of corrective actions taken, and  2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit of this permit.
(6) Ground stabilization measures	After each phase of grading	<ol> <li>The phase of grading (installation of perimeter E&amp;SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover).</li> <li>Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.</li> </ol>

agency inspectors at all times during normal business hours, unless the s a site-specific exemption based on unique site conditions that make th practical:

Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.

EFFECTIVE: 04/01/19

, RECORDKEEPING AND REPORTING

SELF-INSPECTION

CAROLINA NORTH (Environ

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

OYSTER CREEK LANDING US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA

**SDP 2022-305 PERMIT SET** 


**MCKIM& CREED** 

Wilmington, North Carolina 28401

Phone: (910)343-1048, Fax: (910)251-8282


www.mckimcreed.com

**EROSION CONTROL DETAILS** 



I:\09110\0001\ENG\80-DRAWINGS\81\_PRODUCTION\_SHEETS\2\_WORKING\_DWGS\C13.0 GRADING AND DRAINAGE DETAIL.DWG ---- 06/07/2023 14:24:10





- 2" ASPHALT TYPE SF9.5A NCDOT - 8" COMPACTED ABC SAWCUT EXISTING PAVEMENT (NCDOT REQUIRES 16") EXISTING ASPHALT PAVEMENT - SAWCUT EXISTING PAVEMENT 851 NORTH HARVARD AVE. LINDSAY, CA 93247 TOLL FREE: 1-800-726-1994 PHONE: (559) 562-9888 FAX: (559) 562-4488 — USE ONLY DURASLOPE CLASS "A" & "B" GRATES WITH THIS APPLICATION. — SECTION AT DURASLOPE CHANNEL \* BACKFILL TO BE INSTALLED IN 6" LIFTS (MAXIMUM) AND COMPACTED TO A MINIMUM DENSITY OF 95% AS DÉTERMINED BY THE MODIFIED A.A.S.H.T.O. STANDARD METHOD T-99 \* CUT - BACK TO BE PREPARED AFTER TRENCH BACKFILLING AND COMPACTION STANDARD SHOWING METHOD MAKING PAVEMENT REPAIRS WHERE PIPE IS INSTALLED PAVEMENT REPAIR DETAIL PAVEMENT REPAIR DETAIL COMPACTED BACKFILL TO EXISTING GROUND 95% MODIFIED PROCTOR IF UNDER PAVEMENT COMPACTED BACKFILL TO 90% MODIFIED PROCTOR I. CHANNELS TO BE INSTALLED WITH BLANK GRATE. GRATE TO BE PROTECTED FROM CONCRETE POUR (COVER HOLES WITH TAPE). SLOPE WALLS TO ANGLE OF REPOSE OF SOIL 4. THIS DRAWING IS INTENDED FOR USE BY ARCHITECTS, ENGINEERS, CONTRACTORS, CONSULTANTS AND DESIGN 5. ALL INFORMATION CONTAINED HEREIN WAS CURRENT AT THE TIME OF DEVELOPMENT BUT MUST BE REVIEWED AND APPROVED COMPACTED PIPE EMBEDMENT TO 90% MODIFIED PROCTOR COMPACTED GRANULAR MATERIAL DURA SLOPE INSTALLATION DETAIL - CLASS 'A' & 'B' 4' ENCASEMENT, REBAR SUSPENSION METHOD W/ PAVERS FIF REQUIRED BY THE ENGINEER STORMWATER PIPE BEDDING PER GUIDELINES FOR BEDDING DETAILS REVISION DATE 3-5-2015 WATER & SEWER PIPE BEDDING TRENCH BOTTOM PER PENDER COUNTY UTILITY DETAILS & SPECIFICATIONS • CONTRACTOR SHALL SUBMIT SHOP DRAWING FOR TRENCH DRAIN AND STANDARD PIPE TRENCH DETAIL

NOT TO SCALE STANDARD PIPE TRENCH DETAIL

FIG. 2 CLASS — C SHAPED BOTTOM LOAD FACTOR Bc=PIPE I.D. **→** 0.5Bc HAND SHAPED FROM ANGULAR BEDDING MATERIAL GUIDELINES FOR BEDDING DETAILS,

PRECAST MANHOLE

- STD. MANHOLE COVER DETAIL MANHOLE STEPS AS SPECIFIED RAM-NEK JOINT MAT'L OR APPROVED EQUAL (TYPICAL) PRECAST MANHOLE SECTION, A.S.T.M. C 478 CRUSHED STONE EXTENDED BASE MAY NOT BE REQUIRED WHERE MANHOLES ARE GREATER THAN 4 FEET INSIDE DIAMETER PRECAST MANHOLE NOT TO SCALE

DRAWN DCO/ALN VERTICAL:

- EXISTING CONCRETE PAVEMENT

TRENCH BACKFILL COMPACTED

TO 95% MODIFIED PROCTOR


SDP 2022-305 PERMIT SET

GRADING AND DRAINAGE DETAILS


OYSTER CREEK LANDING

US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA


I:\09110\00001\ENG\80-DRAWINGS\81 PRODUCTION SHEETS\2 WORKING DWGS\C13.0 GRADING AND DRAINAGE DETAIL.DWG ---- 06/07/2023 14:24:22



I:\09110\0001\ENG\80-Drawings\81\_Production\_Sheets\2\_Working\_Dwgs\C13.0 GRADING AND DRAINAGE DETAIL.dwg, 6/7/2023 2:24:26 PM, \_DWG To PDF-2016.p




I:\09110\0001\ENG\80-Drawings\81\_Production\_Sheets\2\_Working\_Dwgs\C13.0 GRADING AND DRA



I:\09110\0001\ENG\80-Drawings\81\_Production\_Sheets\2\_Working\_Dwgs\C13.0 GRADING AND DRAINAGE DETAIL.dwg, 6/7/2023 2:24:36 PM, \_I

I:\09110\00001\ENG\80-DRAWINGS\81\_PRODUCTION\_SHEETS\2\_WORKING\_DWGS\C13.0 GRADING AND DRAINAGE DETAIL.DWG ---- 06/07/2023 14:24:36




TAPPING SLEEVE AND VALVE ASSEMBLY DETAIL


NOT TO SCALE


TAPPING SLEEVE AND VALVE ASSEMBLY


STANDARD DETAIL

VERSION #3 - FEB 2016









FIRE HYDRANT ASSEMBLY

STANDARD DETAIL

VERSION #2 - APRIL 2016

PCU STANDARD NOTES

- 1. A PRE-CONSTRUCTION MEETING IS REQUIRED BEFORE BEGINNING WORK. THE MEETING MUST BE SCHEDULED WITH PENDER COUNTY UTILITIES (PCU) AT LEAST ONE WEEK IN ADVANCE. ATTENDEES MUST INCLUDE PCU, THE UTILITY CONTRACTOR'S SUPERINTENDENT, THE SUPPLIER, AND THE CONSULTING ENGINEER.
- 2. ALL MATERIALS USED SHALL CONFORM TO PENDER COUNTY UTILITIES REQUIREMENTS. NON-CONFORMING MATERIAL WILL NOT BE ACCEPTED FOR FINAL CERTIFICATION.
- 3. ALL PIPE SHALL BE C900 DR18 PVC, UNLESS OTHERWISE NOTED (SEE PCU STANDARD DETAIL). PVC PIPE TO BE SDR 21 WHERE C900 IS UNAVAILABLE. THE USE OF DUCTILE IRON PIPE (DIP) IS REQUIRED UNDER PAVED AREAS. PCU MUST APPROVE THE USE OF DIP IN THE FIELD BEFORE INSTALLATION IN OTHER LOCATIONS.
- 4. PCU STANDARD WATERLINE PIPE RESTRAINING METHOD IS MJ GRIP RINGS. AT A MINIMUM ALL FITTINGS, VALVES, ETC. MUST BE RESTRAINED (SEE PCU STANDARD DETAIL).
- 5. PCU MUST INSPECT CASING INSTALLATIONS PRIOR TO BACKFILL. PCU MUST WITNESS PRESSURE TESTS, AND WITHDRAWAL OF BACTERIOLOGICAL SAMPLES. CONTACT PCU UTILITIES INSPECTOR TO SCHEDULE.
- 6. CLOSE-OUT DOCUMENTS WHICH MUST BE RECEIVED PRIOR TO PCU SIGNING THE NCDEQ PWSS APPLICANT CERTIFICATION INCLUDE: BACTERIOLOGICAL TESTS, PRESSURE TESTS, DEED OF DEDICATION, AFFIDAVIT/RELEASE OF LIENS, WARRANTY, AND RECORD DRAWINGS (PDF & CAD).
- 7. AN 18-MONTH WARRANTY PERIOD APPLIES TO ALL WATERLINE CONSTRUCTION. THIS WARRANTY PERIOD DOES NOT BEGIN UNTIL FINAL APPROVAL OF THE SYSTEM HAS BEEN RECEIVED FROM NCDEQ PWSS.

PENDER COUNTY UTILITIES 605 EAST FREMONT STREET PO BOX 995, BURGAW, NC 28425

STANDARD NOTES PCU WATER SYSTEMS VERSION #3 - APRIL 2022

**SMEKIM&CREED** 

Phone: (910)343-1048, Fax: (910)251-8282

Wilmington, North Carolina 28401

www.mckimcreed.com

TEMPORARY BLOW-OFF ASSEMBLY

FIRE HYDRANT ASSEMBLY

PENDER COUNTY UTILITIES


605 EAST FREMONT STREET

BURGAW, NC 28425

STANDARD NOTES

OYSTER CREEK LANDING US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA

UTILITY DETAILS




SDP 2022-305 PERMIT SET

HAMPSTEAD STATION, LLC




- 1. ALL EXISTING VEGETATION THAT IS USED TO MEET LANDSCAPING REQUIREMENTS, ALL REQUIRED PLANTED LIVING MATERIAL. AND ALL REQUIRED BERMS SHALL BE MAINTAINED BY THE OWNER OF THE PROPERTY ON A CONTINUING BASIS. ANY PLANTED MATERIAL WHICH BECOMES DAMAGED OR DISEASED OR DIES SHALL BE REPLACED BY THE OWNER WITHIN 60 DAYS OF THE OCCURRENCE OF SUCH CONDITION. IF, IN THE OPINION OF THE ZONING ADMINISTRATOR THERE ARE SEASONAL CONDITIONS WHICH WILL NOT PERMIT THE TIMELY REPLACEMENT OF THE VEGETATION (E.G. TOO HOT OR TOO COOL FOR SUCCESSFUL REPLANTING) THIS REQUIREMENT MAY BE ADMINISTRATIVELY WAIVED UNTIL A TIME CERTAIN WHEN THE REPLANTING WOULD BE SUCCESSFUL.
- VERIFICATION OF TOTAL LANDSCAPE MATERIAL QUANTITIES AS SHOWN ON THE LANDSCAPE PLANS AND IN THE PLANT SCHEDULE SHALL BE THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR. THE LANDSCAPE ARCHITECT SHALL BE NOTIFIED OF ANY DISCREPANCIES PRIOR TO FINAL BIDDING OR INSTALLATION.
- 3. ALL PLANTING TYPES SHALL COMPLY WITH LOCAL GOVERNING CODES AND REGULATIONS, CONFORM TO REQUIREMENTS OF PLANT LIST AND TO THE AMERICAN ASSOCIATION OF NURSERYMEN "AMERICAN STANDARD OF NURSERY STOCK" AND "HORTICULTURAL STANDARDS" AS TO SPECIES, AGE, SIZE, AND PLANTING RECOMMENDATIONS.
- 4. LANDSCAPE MATERIAL PLACED IN PREPARED HOLES SHALL BE PROPERLY BACKFILLED PRIOR TO THE END OF
- 5. ALL SAUCERS SHALL BE SOAKED WITH WATER AND MULCHED IMMEDIATELY FOLLOWING INSTALLATION. 6. LANDSCAPE ARCHITECT SHALL APPROVE ANY ON-SITE PLANT STORAGE AREA FOR ACCESSIBILITY, SHADE
- CONDITIONS, HEALING-IN MULCH MATERIAL AND TEMPORARY WATERING METHODS.
- 7. ALL ROPE AND WRAPPING TWINE SHALL BE CUT AND REMOVED FROM AROUND THE UPPER PARTS OF THE ROOT BALL. METAL BASKET WIRES AND BURLAP SHALL BE PULLED BACK AND TUCKED UNDER THE EDGES OF THE SAUCER RINGS ON ALL TREES AND LARGE SHRUBS. ALL SYNTHETIC BURLAP SHALL BE REMOVED FROM PLANT BALLS PRIOR TO BACK FILLING.
- 8. ALL PLANT BEDS OR RAISED SAUCER RINGS SHALL BE EDGED WITH SMOOTH, CONTINUOUS CURVES.
- 9. ALL PLANT MATERIAL SHALL BE PLANTED AT HEIGHTS AND WIDTHS AS ILLUSTRATED IN PLANTING DETAILS.
- 10. TREE GUYING SHALL BE PERFORMED WITHIN A WEEK OF PLANTING. THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL TREE GUYING STRAPPING AND STAKES AFTER THE FIRST FULL GROWING SEASON OR ONE YEAR, WHICH EVER COMES FIRST
- 11. CONTRACTOR SHALL VERIFY LOCATIONS OF UNDERGROUND UTILITIES PRIOR TO PLANTING.
- 12. ANY EXPOSED OR UNCOVERED LINES SHALL BE SHOWN TO GENERAL CONTRACTOR PRIOR TO BACKFILLING.
- 13. ALL PLANT BEDS AND RAISED SAUCER RINGS SHALL BE GRADED TO PROVIDE ADEQUATE DRAINAGE AND SHALL BE MULCHED AS SPECIFIED.
- 14. ALL MATERIALS, PLANTING AND LANDSCAPE WORK SHALL CONFORM TO THE CURRENT MUNICIPAL AUTHORITIES STANDARD SPECIFICATIONS AND DETAILS.
- 15. ALL LANDSCAPE AREAS THAT ARE NOT PLANTED, MULCHED OR PAVED SHALL BE SEEDED OR SODDED.
- 16. FIRST YEAR PRUNING OF TREE CROWN SHALL BE LIMITED TO REMOVAL OF DEAD & DAMAGED WOOD. 17. TREE PROTECTION FENCE SHALL BE INSTALLED, INSPECTED AND APPROVED PRIOR TO CLEARING, GRADING AND CONSTRUCTION ACTIVITY OR ISSUANCE OF ANY RELATED PERMITS. NO CONSTRUCTION WORKERS, TOOLS, MATERIALS OR VEHICLES ARE PERMITTED WITHIN THE TREE PROTECTION FENCING.
- 18. MULCH LINE SHALL CONSIST OF SMOOTH CONTINUOUS CURVES.
- 19. ALL TREES NOT WITHIN A PLANT BED SHALL BE TREATED WITH A 6' DIAMETER MULCH RING TYPICAL, UNLESS OTHERWISE INDICATED ON THE PLANTING PLANS.
- 20. TREES SHALL BE LOCATED A MINIMUM OF 5 FEET FROM SEWER/WATER CONNECTIONS OR AS OTHERWISE DICTATED BY LOCAL REGULATIONS. CONTRACTOR SHALL BE LIABLE FOR DAMAGE TO ANY AND ALL PUBLIC OR PRIVATE UTILITIES.
- 21. SUBSTITUTIONS OF PLANT MATERIALS SPECIFIED CAN ONLY OCCUR WITH PRIOR APPROVAL BY LANDSCAPE
- 22. ESTABLISH PLANT BED CONFIGURATION. LANDSCAPE ARCHITECT TO APPROVE BED LAYOUT IN FIELD. 23. AREAS DAMAGED BY ACTIVITIES OF CONTRACTOR SHALL BE RE-ESTABLISHED TO PRE-DISTURBANCE CONDITION
- AT NO ADDITIONAL COST TO THE OWNER. 24. USE HERBICIDES, PESTICIDES, AND FERTILIZER IN A MANNER CONSISTENT WITH THE FEDERAL INSECTICIDE,
- FUNGICIDE, AND RODENTICIDE ACT AND IN ACCORDANCE WITH LABEL RESTRICTIONS.
- 25. CONTRACTOR SHALL INSURE THAT ALL PLANT MATERIAL IS FREE OF FIRE ANTS PRIOR TO INSTALLATION.
- 26. LANDSCAPE ARCHITECT OR OWNER SHALL APPROVE PLACEMENT OF TREES PRIOR TO PLANTING. 27. STREET TREES SHALL BE MAINTAINED TO PROVIDE 13'-6" CLEAR HEIGHT FOR THE PORTION OF THE TREE
- CANOPY THAT EXTENDS OVER THE VEHICULAR NETWORK.
- 28. STREET TREES SHALL BE LOCATED A MINIMUM OF 15 FEET FROM STREETLIGHTS. 29. LANDSCAPING OR PARKING CANNOT BLOCK OR IMPEDE THE FDC OR FIRE HYDRANTS. A 3-FOOT CLEAR SPACE
- SHALL BE MAINTAINED AROUND THE CIRCUMFERENCE OF THE HYDRANT AND FDC. 30. DEEPROOT ROOT BARRIER OR APPROVED EQUAL SHALL BE INSTALLED AT ALL STREET TREE LOCATIONS AND WHERE A TREE IS WITHIN 10' OF A UTILITY OR HARDSCAPE. THE ROOT BARRIER SHALL BE INSTALLED
- ACCORDING TO MANUFACTURER RECOMMENDATION. 31. LANDSCAPE CONTRACTOR SHALL PROVIDE IRRIGATION DESIGN AND INSTALL IRRIGATION SYSTEM.
- 32. MULCH SHALL BE SHREDDED HARDWOOD, SPREAD AT THICKNESS OF 3" DEEP ACROSS PLANTING AREAS.



SHRUB SCHEDULE						
SHRUBS	SIZE	HEIGHT	SPREAD	SPACING	QTY	REMARKS
BUXUS MICROPHYLLA 'WINTERGREEN' WINTERGREEN BOXWOOD	7 GAL.	24" HT. MIN.	24"-30" SPD.	3` O.C.	87	MATCHED
ILEX GLABRA `SHAMROCK` INKBERRY	3 GAL.	24" HT. MIN.	24"-30" SPD.	3.5` O.C.	154	UNIFORM HEAD & MATCHED
ILEX VOMITORIA `NANA` DWARF YAUPON	7 GAL.	24" HT. MIN.	18"-24" SPD.	3` O.C.	79	UNIFORM HEAD & MATCHED
PODOCARPUS MACROPHYLLUS MAKI SHRUBBY YEW	7 GAL.	24" HT. MIN.	24"-30" SPD.	3` O.C.	174	UNIFORM HEAD & MATCHED
ROSA X `MEIGALPIO` TM RED DRIFT GROUNDCOVER ROSE	3 GAL.	12"-15" HT.	12"-15" SPD.	2.5` O.C.	81	UNIFORM HEAD & MATCHED

GROUND COVER	SCHE	DULE		
GROUND COVERS	SIZE	SPACING	QTY	REMARKS
CYNODON DACTYLON BERMUDAGRASS	SOD	-	51,646 SF	
LIRIOPE MUSCARI `BIG BLUE` LIRIOPE	1 QT.	15" O.C.	1,904	MATCHED

5 | PLANT LEGEND



SPACING (A) ROW OFFSET (B) SPACING (A) ROW OFFSET (B) 1'-0" O.C. 4'-4" O.C. 5'-0" O.C. 1'-6" O.C. 1'-4" O.C. 6'-0" O.C. 5'-2" O.C. 2'-0" O.C. 1'-9" O.C. 7'-0" O.C. 6'-1" O.C. 8'-0" O.C. 6'-11" O.C. 2'-6" O.C 2'-2" O.C. 3'-0" O.C. 2'-7" O.C. 9'-0" O.C. 7'-10" O.C. - PLANTING BED 3'-6" O.C. 3'-0" O.C. 10'-0" O.C. 8'-8" O.C. **EDGE** 4'-0" O.C. 3'-6" O.C. GENERAL NOTES: SCARIFY BOTTOM AND SIDES OF PLANTING PIT. THE BOTTOM OF SHRUB ROOT BALLS SHALL NOT PROJECT INTO THE NATIVE SUBGRADE LARGER PLANTS WILL REQUIRE ADDITIONAL TOPSOIL DEPTH. BACKFILL PLANTING PITS WITH TOPSOIL MIXTURE AS SPECIFIED, INSTALL IN 6" LAYERS, HAND TAMP TO REMOVE VOIDS AND WATER EACH LAYER ALL ROOT BALLS REMOVED FROM CONTAINERS SHALL BE SCARIFIED BY HAND PRIOR TO PLACEMENT AND BACKFILLING WITH PREPARED SOILS. HAND TOOLS SHALL NOT BE USED TO SCARIFY ROOT BALLS. SHRUB AS SPECIFIED PER LANDSCAPE PLAN(S **ROOT CROWN TO BE SET** 2" ABOVE EXISTING GRADE MIN. PLANT SPACING PLANT SPACING 4" DEEP SHOVEL DUG "V AS SPECIFIED AS SPECIFIED TRENCH, SEE LANDSCAPE PLAN FOR LOCATIONS ADJACENT TURF AREA REFER TO PLANTING PLAN FOR LOCATIONS MULCH AS SPECIFIED **KEEP 4" AWAY FROM** SHRUB ROOT BALL ROOT CROWN NATIVE SOIL, TILL SOIL <u>SECTION</u> NATIVE SUBGRADE TO A 6" MIN. DEPTH **TOPSOIL** 

PLANT SPACING A. SCARIFY BOTTOM AND SIDES OF PLANTING PIT B. THE BOTTOM OF GROUND COVER ROOT BALLS SHALL NOT PROJECT INTO THE NATIVE SUBGRADE LARGER PLANTS WILL REQUIRE ADDITIONAL TOPSOIL DEPTH. BACKFILL PLANTING PITS WITH TOPSOIL MIXTURE AS SPECIFIED, INSTALL IN 6" LAYERS, HAND TAMP TO REMOVE VOIDS AND WATER EACH LAYER ALL ROOT BALLS REMOVED FROM CONTAINERS SHALL BE SCARIFIED BY HAND PRIOR TO PLACEMENT AND BACKFILLING WITH PREPARED SOILS. HAND TOOLS SHALL NOT BE USED TO SCARIFY ROOT BALLS. EQUAL TO SHRUB AS SPECIFIED THE PLANT SPACING PER LANDSCAPE PLAN(S) AS SPECIFIED (TYP.) ROOT CROWN TO BE SET - PLANT SPACING 2" ABOVE EXISTING AS SPECIFIED (TYP.) GRADE MIN. 4" DEEP SHOVEL DUG "V" TRENCH, SEE LANDSCAPE PLAN FOR LOCATIONS ADJACENT TURF AREA, REFER TO PLANTING PLAN FOR LOCATIONS 4" MIN. MULCH AS SPECIFIED. GROUND COVER ROOT KEEP 4" AWAY FROM TREE TRUNK <u>SECTION</u> NATIVE SOIL, TILL SOIL NATIVE SUBGRADE TO A 6" MIN. DEPTH TYPICAL GROUND COVER PLANTING

PLANT SPACING CHART

6" O.C.

8" O.C.

12" O.C.

15" O.C.

18" O.C.

ROW OFFSET (B) SPACING (A)

24" O.C.

36" O.C.

4'-0" O.C.

5'-0" O.C.

6'-0" O.C.

5" O.C.

7" O.C.

1'-1" O.C.

1'-4" O.C.

ROW OFFSET (B)

2'-7" O.C.

3'-6" O.C.

4'-4" O.C.

5'-2" O.C.

1'-9" O.C.

GENERAL LANDSCAPE NOTES







License: F-1222

www.mckimcreed.com

OYSTER CREEK LANDING

US HIGHWAY 17, HAMPSTEAD, PENDER COUNTY, NORTH CAROLINA

LANDSCAPE DETAILS

SCALE DRAWN DESIGNED ALM/THL PROJ. MGR.

HORIZONTAL VERTICAL: ----

ISSUED FOR BIDS

HAMPSTEAD STATION, LLC

TYPICAL SHRUB PLANTING